PROJECT GENERAL NOTES

1. THESE GENERAL NOTES ARE INTENDED TO COMPLIMENT THE CONTRACT DOCUMENTS. REFER TO THE CONTRACT DOCUMENTS FOR DETAILED INFORMATION AND ADDITIONAL REQUIREMENTS.

2. ALL WORK INCLUDED IN THIS CONTRACT SHALL CONFORM TO ALL FEDERAL, STATE, AND LOCAL LAWS, STATUTES, ORDINANCES, CODES, RULES AND REGULATIONS, OR LAWFUL ORDERS OF PUBLIC AUTHORITY. PROMPTLY REPORT ANY NONCONFORMITY DISCOVERED TO THE ARCHITECT.

3. THE INTENT OF THE CONTRACT DOCUMENTS IS TO INCLUDE ALL ITEMS NECESSARY FOR THE PROPER EXECUTION AND COMPLETION OF WORK BY THE CONTRACTOR AND TO PROVIDE A COMPLETE, FULLY OPERATIONAL BUILDING. PROVIDE ALL LABOR, MATERIALS AND INCIDENTALS NECESSARY TO ACHIEVE THIS INTENT.

4. FAILURE OF THE DRAWINGS OR SPECIFICATIONS TO INDICATE EACH INCIDENTAL SHALL NOT RELIEVE THE CONTRACTOR FROM PROVIDING THE NECESSARY ITEMS AS PART OF THIS CONTRACT. THE DRAWINGS SHOW THE DESIGN, LOCATION, DESCRIBE THE QUALITY LEVEL AND CONSTRUCTION TECHNIQUES IN A GENERAL SENSE ONLY.

5. ALL DETAILS ARE TYPICAL. WHAT IS SHOWN IN ONE CONDITION APPLIES TO ALL OTHER SIMILAR CONDITIONS, UNLESS NOTED OTHERWISE.

6. VERIFY THE FOLLOWING ITEMS AND REPORT ANY DISCREPANCIES TO THE ARCHITECT PRIOR TO PROCEEDING WITH WORK, AND PROCEED WITH THE WORK ONLY AFTER SUCH DISCREPANCIES ARE RESOLVED.
   - EXISTING CONDITIONS
   - WALLS, FLOORS, ROOFS, AND SUBSTRATES WHERE PRODUCTS AND SYSTEMS ARE TO BE INSTALLED.
   - SIZE AND CONDITION OF WINDOW, DOOR, LOUVER, AND OTHER OPENINGS WHERE PRODUCTS AND SYSTEMS ARE TO BE INSTALLED.
   - THE EXISTENCE, SIZE, AND LOCATION OF ALL EXISTING UTILITIES, MECHANICAL AND ELECTRICAL SYSTEMS.
   - DISCREPANCIES BETWEEN OR WITHIN THE CONTRACT DOCUMENTS.
   - UNSUITABLE SOILS: REPORT THE LOCATION OF ALL UNSUITABLE SOIL MATERIALS BELOW ANTICIPATED LEVELS OF FOOTINGS OR SLABS PRIOR TO SETTING FORMS.
   - MECHANICAL, ELECTRICAL AND PLUMBING WHICH IMPACT CEILING INSTALLATION HEIGHTS OR BUILDING THE APPEARANCE.
   - DIMENSIONAL DISCREPANCIES.

7. COORDINATE THE WORK OF ALL SUBCONTRACTORS.

8. DO NOT PENETRATE STRUCTURAL BEAMS, COLUMNS, OR SHEAR WALLS UNLESS SPECIFICALLY DETAILED OTHERWISE.

9. PROVIDE BOND-OUTS, BLOCKING, SLEEVES AND PIPES AS REQUIRED FOR ALL WALL, FLOOR, ROOF, AND CEILING PENETRATIONS.
   - MAINTAIN CONTINUITY OF FIRE RATED ASSEMBLIES AND SMOKE ASSEMBLIES. SEAL ALL PENETRATIONS TO CONFORM TO U.L. RATED ASSEMBLIES AND ALL NFPA AND IBC REQUIREMENTS. REFER TO THE CODE PLANS FOR ADDITIONAL CODE REFERENCES.
   - ALL PENETRATIONS SHALL COMPLY WITH THE ACOUSTICAL ASSEMBLY RATING REQUIRED FOR EACH WALL OR FLOOR ASSEMBLY.

10. COORDINATE THE WORK TO ACHIEVE THE GIVEN VISUAL AND PERFORMANCE REQUIREMENTS OF MECHANICAL, ELECTRICAL AND PLUMBING SYSTEMS WITHIN THE INDICATED SPACE.

11. PROVIDE WORK HOLES OR ADEQUATE ACCESS AS REQUIRED TO INSTALL NEW SYSTEMS IN CONCEALED SPACES.

12. PRODUCTS SHALL BEAR UL CLASSIFICATION WHERE REQUIRED BY DESIGN. DO NOT REMOVE OR PAINT OVER UL CLASSIFICATIONS.

13. **DEFINITIONS:**
   - **NEW:** INDICATES ITEMS THAT SHALL BE FURNISHED AND INSTALLED BY THIS CONTRACT. TYPICALLY USED TO ENSURE CLARITY BETWEEN VARIOUS COMPONENTS OF THE DRAWINGS, NOT ALL ITEMS ARE LABELED AS "NEW" WHEN IT IS OBVIOUS BY OTHER INDICATION.
   - **EXISTING:** EXISTING BUILDING OR SITE COMPONENTS WHICH ARE IN PLACE AT THE START OF CONSTRUCTION. NOT ALL ITEMS ARE LABELED AS "EXISTING" WHEN IT IS OBVIOUS BY OTHER INDICATION.
   - **REPAIR:** RESTORE TO SUITABLE OR APPROPRIATE OPERATING AND AESTHETIC CONDITION.
   - **RESTORE:** BRING BACK TO FORMER CONDITION, BY REPAIRING OR PATCHING AS REQUIRED.
   - **PATCH:** RESTORE TO CONDITION MATCHING EXISTING ADJACENT CONSTRUCTION, SURFACE TEXTURE AND FINISH.
   - **N.I.C.** (NOT IN CONTRACT): WORK WHICH IS NOT INCLUDED IN THIS CONTRACT, BUT WHICH MAY REQUIRE CONTRACTOR COORDINATION.
   - **REMOVE:** DISMANTLE AND/OR EXTRACT FROM THE PREMISES ENTIRELY. DISPOSE OF OFF OF THE SITE UNLESS NOTED OTHERWISE.
   - **REPLACE:** DISMANTLE AND/OR EXTRACT FROM THE PREMISES ENTIRELY. DISPOSE OF OFF OF THE SITE UNLESS NOTED OTHERWISE. PROVIDE NEW MATERIAL AS INDICATED.
   - **DAMAGES:** EXISTING BUILDING OR SITE COMPONENTS, NOT SCHEDULED FOR WORK, WHICH ARE DAMAGED. SUCH ELEMENTS AND COMPONENTS SHALL BE REPLACED OR RESTORED TO ORIGINAL CONDITION BY METHODS APPROVED BY THE ARCHITECT.
   - **DEMOLISH:** DISMANTLE AND/OR EXTRACT FROM THE PREMISES ENTIRELY. DISPOSE OF OFF OF THE SITE UNLESS NOTED OTHERWISE.
   - **SALVAGE:** REMOVE AND REINSTALL OR REMOVE AND DELIVER TO THE OWNER, AS INDICATED. SALVAGED COMPONENTS MAY BE FOR LIMITED REUSE, TO MATCH EXISTING CONDITIONS OR TO PATCH AND REPAIR AS INDICATED.

GENERAL ARCHITECTURAL NOTES

1. THE DRAWINGS USE A SYSTEM OF KEYED NOTES ON PLANS, ELEVATIONS AND DETAILS. INSTRUCTIONS FOR SPECIFIC COMPONENTS OF THE WORK ARE KEYED TO THE DRAWINGS. BUILDING SYSTEMS (PARTITIONS, ROOF & FOUNDATION) ARE KEYED TO FLOOR PLANS, WALL SECTIONS, ROOF PLAN AND OTHER DETAILS AS APPROPRIATE.

2. MAINTAIN MINIMUM MANEUVERING CLEARANCES AT DOORS IN COMPLIANCE WITH THE ADA ACCESSIBILITY GUIDELINES (ADAAG), INCLUDING BUT NOT LIMITED TO THE FOLLOWING EXCERPT FROM 2010 ADA STANDARDS FOR ACCESSIBLE DESIGN:

   404.2.4.1 Swinging Doors and Gates. Swinging doors and gates shall have maneuvering clearances complying with Table 404.2.4.1.

   Table 404.2.4.1 Maneuvering Clearances at Manual Swinging Doors and Gates

Type of Use		Minimum Maneuvering Clearance	
Approach Direction	Door or Gate Side	Perpendicular to Doorway	Parallel to Doorway (beyond latch side unless noted)
From front	Pull	60 inches (1525 mm)	18 inches (455 mm)
From front	Push	48 inches (1220 mm)	0 inches (0 mm)[1]
From hinge side	Pull	60 inches (1525 mm)	36 inches (915 mm)
From hinge side	Pull	54 inches (1370 mm)	42 inches (1065 mm)
From hinge side	Push	42 inches (1065 mm)[2]	22 inches (560 mm)[3]
From latch side	Pull	48 inches (1220 mm)[4]	24 inches (610 mm)
From latch side	Push	42 inches (1065 mm)[4]	24 inches (610 mm)

   1. Add 12 inches (305 mm) if closer and latch are provided.
   2. Add 6 inches (150 mm) if closer and latch are provided.
   3. Beyond hinge side.
   4. Add 6 inches (150 mm) if closer is provided.

3. ALL MOUNTING HEIGHTS AND CLEARANCES AT TOILET ROOMS AND ELSEWHERE SHALL COMPLY WITH THE LATEST VERSION OF THE ADA ACCESSIBILITY GUIDELINES (ADAAG).
   - BARRIER-FREE CLEARANCES ARE GIVEN. THESE **CLEAR** DIMENSIONS SHALL BE MAINTAINED IN CASES OF DISCREPANCY.
   - ALL DIMENSIONS GIVEN FOR FIXTURE AND ACCESSORY LOCATIONS ARE **CLEAR** DIMENSIONS FROM FINISHED SURFACES, UNLESS NOTED OTHERWISE. COORDINATE ACTUAL DIMENSIONS WITH WALL CONSTRUCTION AND FINISHES.
   - LOCATE ALL CONTROLS, FLUSH VALVES, SHUTOFFS AND SIMILAR ITEMS IN ACCORDANCE WITH THE LATEST VERSION OF THE ADA ACCESSIBILITY GUIDELINES (ADAAG).
   - SOME ITEMS MAY INDICATE A RANGE IN MOUNTING HEIGHT. MAINTAIN A CONSISTENT MOUNTING HEIGHT, WITHIN THE GIVEN RANGE, THROUGHOUT THE PROJECT, UNLESS NOTED OTHERWISE.

4. MAINTAIN **CLEAR** DIMENSIONS IN ACCORDANCE WITH THE LATEST VERSION OF THE ADA ACCESSIBILITY GUIDELINES (ADAAG).

5. ALL GRAB BAR COMPONENTS SHALL BE ABLE TO WITHSTAND A LOAD OF 250LBS AT ANY POINT.

6. INSTALL BLOCKING BEHIND ALL SURFACE-APPLIED FIXTURES, TRIM, GRAB BARS, SHELVES, CHAIR RAILS, PICTURE RAILS, BASE MOLDINGS, TACK OR MARKER BOARDS, WINDOW TREATMENT, WALL OR BASE CABINETS OR COUNTERS, AND MISCELLANEOUS ACCESSORIES MOUNTED ON STUD WALLS.

7. ALL EXPOSED WOOD NOT INDICATED TO BE PAINTED SHALL BE NATURAL FINISH (CLEAR).

8. FLOORING AND FLOOR FINISHES SHALL BE INSTALLED TO A MAXIMUM DIFFERENTIAL OF 1/16" BETWEEN DISSIMILAR MATERIALS. PROVIDE TRANSITION STRIPS OR THRESHOLDS (1/2" MAXIMUM) OF SAME MATERIAL AS FLOORING AND/OR AS NOTED ON THE DRAWINGS, BETWEEN DISSIMILAR FLOORING MATERIALS

9. PATCH AND LEVEL EXISTING SUBFLOORS TO RECEIVE NEW FLOOR FINISHES AS INDICATED IN THE ROOM FINISH SCHEDULE.

10. ALL EXPOSED PIPES UNDER LAVATORIES AND SINKS SHALL BE INSULATED OR OTHERWISE CONFIGURED TO PROTECT AGAINST CONTACT.

11. INSTALL 2 COAT HOOKS CENTERED ON THE INSIDE OF SINGLE USER TOILET ROOM DOORS, MOUNTED AT 48"AFF AND 60"AFF.

ROOF GENERAL NOTES

1. PROTECT ALL OPENINGS CUT IN THE ROOF. PROVIDE TEMPORARY ROOFING IF WORK IS TO BE UNFINISHED DURING ADVERSE WEATHER CONDITIONS THROUGHOUT THE CONSTRUCTION PHASE.

2. PROVIDE FLASHING AT ALL ROOF PENETRATIONS. PENETRATIONS MAY NOT BE INDICATED ON THE ROOF PLAN. REFER TO STRUCTURAL, MECHANICAL AND ELECTRICAL PLANS FOR NUMBER, LOCATION, AND SIZE OF PENETRATIONS.

3. PROVIDE A 2 FEET WIDE WALKWAY WITH PROTECTION STRIPS ENTIRELY AROUND ALL ROOF TOP MECHANICAL UNITS AND CREATE A PROTECTION STRIP PATHWAY, 2 FEET WIDE, FROM THE ROOF ACCESS LOCATION(S) TO EACH MECHANICAL UNIT.

4. PROTECT ROOFING MATERIALS FROM CONSTRUCTION OPERATIONS.

5. PROVIDE CURBS AND PRESSURE TREATED WOOD BLOCKING AS REQUIRED FOR ALL ROOF MOUNTED EQUIPMENT, UNLESS NOTES OTHERWISE.

6. COORDINATE LOCATION OF ROOF TOP EQUIPMENT TO PROVIDE SAFE ACCESS FOR SERVICE. PROVIDE FALL PROTECTION IN THE EVENT EQUIPMENT IS LOCATED WITHIN 10' OF ROOF EDGE AND PARAPET DOES NOT EXIST.

VERTICAL CIRCULATION GENERAL NOTES

1. ALL HANDRAIL AND GUARDRAIL COMPONENTS SHALL BE ABLE TO WITHSTAND A HORIZONTAL LOAD OF 250 POUNDS AT ANY POINT.

2. GUARDRAILS SHALL NOT ALLOW THE PASSAGE OF A 4-INCH SPHERE BETWEEN MEMBERS.

3. ALL RAMP, STAIR, LADDER, ALTERNATING TREAD DEVICE, HANDRAIL AND GUARDRAIL COMPONENTS SHALL COMPLY WITH THE APPLICABLE PROVISIONS OF THE LATEST VERSION(S) IBC, NFPA 101, AND THE ADA.

ABBREVIATIONS

AB	ANCHOR BOLT
AB	AIR BARRIER
AC	AIR CONDITIONING
ADDL	ADDITIONAL
ADJ	ADJUSTABLE
ADO	AUTOMATIC DOOR OPERATOR
AFF	ABOVE FINISHED FLOOR
AH	AIR HANDLER
AIB	AIR INFILTRATION BARRIER
ALT	ALTERNATE
ALUM	ALUMINUM
AOR	AREA OF REFUGE
APPROX	APPROXIMATE
ARCH	ARCHITECT(URAL)
ARND	AROUND
AVB	AIRVAPOR BARRIER
AWP	ACOUSTICAL WALL PANEL
BD	BOARD
BF	BARRIER FREE
BIT	BITUMINOUS
BLDG	BUILDING
BLKG	BLOCKING
BM	BENCHMARK
BOT	BOTTOM
BO	BOTTOM OF
BRK	BRICK
BRG	BEARING
B/S	BRICK SHELF
BSMT	BASEMENT
C, CRS	COURSE
CAB	CABINET
CB	CATCH BASIN
CC	CENTER TO CENTER
CF	CUBIC FOOT
CFMF	COLD FORMED METAL FRAMING
CJ	CONTROL JOINT
CL	CENTERLINE
CLG	CEILING
CLR	CLEAR
CMT	CERAMIC MOSAIC TILE
CMU	CONCRETE MASONRY UNIT
CO	CLEANOUT
COL	COLUMN
CONC	CONCRETE
CONC/C	COLORED CONCRETE
CONT	CONTINUOUS OR CONTINUE
CONTR	CONTRACTOR
CPT	CARPET
CS	COUNTERSINK
CSMT	CASEMENT
CT	CERAMIC TILE
CWT	CERAMIC WALL TILE
CUH	CABINET UNIT HEATER
CY	CUBIC YARD
DBL	DOUBLE
DC	DISPLAY CASE
DEMO	DEMOLISH, DEMOLITION
DF	DRINKING FOUNTAIN
DIA, DIAM	DIAMETER
DIM	DIMENSION
DIV	DIVISION
DMP	DEMOUNTABLE PARTITION
DN	DOWN
DR	DOOR
DTL	DETAIL
DWG	DRAWING
DWR	DRAWER
E	EAST
EA	EACH
EF	EXHAUST FAN
EMHO	ELECTRO MAGNETIC HOLD OPEN
EIFS	EXTERIOR INSULATION FINISH SYSTEM
EJ	EXPANSION JOINT
EL	ELEVATION
EP	EPOXY PAINT
ELEC	ELECTRICAL
ELEV	ELEVATOR
EMER	EMERGENCY
ENCL	ENCLOSED/ENCLOSURE
EQ	EQUAL
EQUIP	EQUIPMENT
EXH	EXHAUST
EXIST	EXISTING
EXT	EXTERIOR
EW	EYEWASH
EWC	ELECTRIC WATER COOLER
FB	FIRE BLANKET
FBO	FURNISHED BY OWNER
FCS	FLOOR COATING SYSTEM
FD	FLOOR DRAIN
FE	FIRE EXTINGUISHER
FEC	FIRE EXTINGUISHER AND CABINET
FFE	FINISHED FLOOR ELEVATION
FG	FIBERGLASS
FHVC	FIRE HOSE AND VALVE CABINET
FIN	FINISH(ED)
FIN GR	FINISH GRADE
FLR	FLOOR(ING)
FNDN	FOUNDATION
FP	FIREPROOFING
FO	FACE OF
FRMG	FRAME(ING)
FRP	FIBER REINFORCED PLASTIC
FRT	FIRE RETARDANT TREATED
FSR	FLEXIBLE SHEET ROOFING
FT	FOOT(FEET)
FTG	FOOTING
FTR	FIN TUBE RADIATION
FUR	FURRED(ING)
FV	FIELD VERIFY
FWC	FABRIC WALL COVERING
GA	GAUGE
GALV	GALVINIZED
GB	GRAB BAR
GFB	GROUND FACE CMU
GL	GLASS, GLAZING
GWB	GYPSUM WALLBOARD
HARD	HARDENER
HB	HOSE BIBB
HC	HOLLOW CORE
HD	HEAD
HDO	HIGH DENSITY OVERLAY
HDWD	HARDWOOD
HDWR	HARDWARE
HM	HOLLOW METAL
HORIZ	HORIZONTAL
HR	HAND RAIL
HS	HIGH SCHOOL
HT	HEIGHT
HTG	HEATING
HVAC	HEATING/VENTILATION/AIR CONDITIONING
IBC	INSTALLED BY CONTRACTOR
ID	INSIDE DIAMETER
IN	INCH (ES)
INCL	INCLUDE (D), (ING)
INFO	INFORMATION
INSUL	INSULATED
INT	INTERIOR
INV	INVERT
JT	JOINT
KIT	KITCHEN
LAB	LABORATORY
LAM	LAMINATE (D)
LAV	LAVATORY
LB	POUND (S)
LCC	LEAD COATED COPPER
LF	LINEAR FOOT
LH	LEFT HAND
LOC'N	LOCATION
LW	LIGHTWEIGHT (CMU)
MAS	MASONRY
MATL	MATERIAL
MAX	MAXIMUM
MC	MEDICINE CABINET
MCWF	MULTI COLOR WALL FINISH
MDO	MEDIUM DENSITY OVERLAY
MECH	MECHANICAL
MED	MEDIUM
MF	MEMBRANE FLASHING
MFR	MANUFACTURER
MH	MANHOLE
MIN	MINIMUM
MISC	MISCELLANEOUS
MLDG	MOULDING, MOULDING
MO	MASONRY OPENING
MR	MOISTURE RESISTANT
MRGB	MOISTURE RESISTANT GYPSUM BOARD
MS	MOP SINK
MSF	METAL STUD FRAMING
MTL	METAL
N	NORTH
NA	NOT APPLICABLE
NIC	NOT IN CONTRACT
NO	NUMBER
NOM	NOMINAL
NRC	NOISE REDUCTION COEFFICIENT
NTS	NOT TO SCALE
O/	OVER
OC	ON CENTER
OD	OUTSIDE DIAMETER
OFS	OVERFLOW SCUPPER
OP	OPAQUE
OH	OVERHEAD
OPH	OPPOSITE HAND
OPNG	OPENING
OPP	OPPOSITE
OPS	OPERABLE PANEL SYSTEM
P, PTD	PAINT
PC	PRECAST CONC.
PERF	PERFORATED
PERIM	PERIMETER
PRKG	PARKING
PL	PLATE
PLAM	PLASTIC LAMINATE
PLYWD	PLYWOOD
PSF	POUNDS PER SQUARE FOOT
PSI	POUNDS PER SQUARE INCH
PT	PRESSURE TREATED
PTD	PAPER TOWEL DISPENSER
PTN	PARTITION
PVC	POLYVINYL CHLORIDE
PVMT	PAVEMENT
QR	QUARTER ROUND
QT	QUARRY TILE
RE:	REFERENCE
REF	REFRIGERATOR
REQ'D	REQUIRED
REV	REVISION (S), REVISED
RL	RAIN LEADER
RF	RUBBER FLOOR
RH	RIGHT HAND
RM	ROOM
RO	ROUGH OPENING
ROW	RIGHT OF WAY
S	SOUTH
SAT	SUSPENDED ACOUSTICAL TILE
SC	SOLID CORE
SCHED	SCHEDULE
SD	STORM DRAIN, SOAP DISPENSER
SECT	SECTION
SF	SQUARE FOOT
SGL	SAFETY GLASS
SH	SHOWER
SHT	SHEET
SHTHG	SHEATHING
SIM	SIMILAR
SLNT	SEALANT
SNR	SANITARY NAPKIN RECEPTOR
SP	SPECIAL PAINT
SPEC	SPECIFICATION
SPKR	SPEAKER
SQ	SQUARE
SS	STAINLESS STEEL
STC	SOUND TRANSMISSION CLASS
STD	STANDARD
STL	STEEL
STOR	STORAGE
STRL	STRUCTURAL
STRUCT	STRUCTURE/STRUCTURAL
SUPT	SUPPORT
SUSP	SUSPENDED
SV	SHEET VINYL
T	TOILET
TB	TOWEL BAR
TB	TACKBOARD
T&G	TONGUE AND GROOVE
TGL	TEMPERED GLASS
THK	THICK(NESS)
TO	TOP OF
TP	TOILET PARTITION
TPD	TOILET PAPER DISPENSER
TV	TELEVISION
TYP	TYPICAL
UCR	UNDER COUNTER REFRIGERATOR
UNO	UNLESS NOTED OTHERWISE
VB	VAPOR BARRIER/VINY BASE
VC	VALVE CABINET
VCT	VINYL COMPOSITION TILE
VERT	VERTICAL
VPW	VENEER PLYWOOD
VWC	VINYL WALL COVERING
W	WEST
W/	WITH
WC	WATER CLOSET
WD	WOOD
WGL	WIRE GLASS
WH	WATER HEATER
W/O	WITHOUT
WS	WATERSTOP
WP	WATERPROOF
WWF	WELDED WIRE FABRIC
WWM	WELDED WIRE MESH
YD	YARD
ZCC	ZINC-COATED COPPER

MATERIALS LEGEND

GRAVEL
CONCRETE MASONRY UNIT
BRICK
CONCRETE
SOIL
STEEL
WOOD FRAMING
WOOD BLOCKING
GYPSUM BOARD
PLYWOOD
RIGID INSULATION
BATT INSULATION

SYMBOLS

Room name
101 — ROOM TAG
150 SF

101 — DOOR TAG

1t — WINDOW\GLAZING TAG

XX — WALL TAG

1 — SPECIALTY EQUIPMENT\ TOILET ACCESSORY TAG

1i — CASEWORK TAG

— DEMOLITION KEY NOTE

1 A101 — BUILDING SECTION

1 A101 — WALL SECTION

SIM 1 A101 — PLAN OR SECTION DETAIL

SIM 1 A101 — EXTERIOR ELEVATION

1 A41.1 1 — INTERIOR ELEVATION

FLOOR LEVEL\VERTICAL ELEVATION

0.0 — COLUMN CENTERLINE

FIRE RATINGS

SMOKE
1 HOUR FIRE RATED PARTITION
2 HOUR FIRE RATED PARTITION
1/2 HOUR FIRE RATED PARTITION

PDT ARCHITECTS
49 DARTMOUTH STREET
PORTLAND, MAINE
04101
207-775-1059
www.pdtarchs.com

COPYRIGHT
PDT Architects
Reuse or reproduction of the contents of this document is not permitted without written permission of PDT Architects.

Lowell Street 3rd & 4th Floor Renovations
15 Lowell Street, Portland, Maine 04101

#	Date	Description

Revision Schedule

REGISTERED ARCHITECT DAVID C. WEBSTER 923 STATE OF MAINE

JOB NO. 16064

DRWN: Author CHK: Checker

SCALE:

ISSUE: Permit Set
June 16, 2017

TITLE: General Notes & Material Legend

SHEET A001