First & Second Floor (Phase 2) Door & Frame Schedule

LEVEL	LOCATION DOOR NO.	LOCATION ROOM NO.	LOCATION ROOM NAME	DOOR OPENING WIDTH	DOOR OPENING HEIGHT	DOOR PANEL TYPE	DOOR PANEL CONFIG	DOOR PANEL WIDTH	DOOR MATL	FRAME RATING	DOOR HDWR	COMMENTS	Lowell Street Project Phase
1st FLOOR	112	112	Office	3' - 0"	6' - 8"	F	SINGLE	3' - 0"	HM		2		Phase 2
1st FLOOR	116	116	Office	3' - 0"	6' - 8"	F	SINGLE	3' - 0"	HM		2		Phase 2
1st FLOOR	122	122	Office	3' - 0"	6' - 8"	F	SINGLE	3' - 0"	HM		2		Phase 2
1st FLOOR	123	123	Office	3' - 0"	6' - 8"	F	SINGLE	3' - 0"	HM		2		Phase 2
1st FLOOR	123A	123A	Central Supply	3' - 0"	6' - 8"	F	SINGLE	3' - 0"	HM		3	CARD ACCESS	Phase 2
1st FLOOR	123E			3' - 0"	7' - 0"	F	SINGLE	3' - 0"	ETR	90	ETR		Phase 2
1st FLOOR	124.2	128	Lobby	3' - 0"	7' - 0"	F	SINGLE	3' - 0"	ETR	90	3	EXISTING TO REMAIN COORDINATE CARD ACCESS	Phase 2
1st FLOOR	124.10	128	Lobby	3' - 0"	6' - 8"	F	SINGLE	3' - 0"	HM		5		Phase 2
1st FLOOR	128.1	128A	Med Records	3' - 0"	6' - 8"	F	SINGLE	3' - 0"	HM		4	CARD ACCESS	Phase 2
1st FLOOR	128.2	C110	Corridor	3' - 0"	6' - 8"	F	SINGLE	3' - 0"	HM		3	CARD ACCESS	Phase 2
1st FLOOR	134.1	134	Exam	3' - 6"	7' - 0"	F	SINGLE	3' - 6"					Phase 2
2nd FLOOR	203.1	206A	Waiting	3' - 0"	7' - 0"	F	SINGLE	3' - 0"	HM		3	CARD ACCESS	Phase 2
2nd FLOOR	206.1	206B	Waiting	3' - 0"	7' - 0"	F	SINGLE	3' - 0"	HM		3	CARD ACCESS	Phase 2
2nd FLOOR	211	211	Exam-Peds	3' - 0"	7' - 0"	F	SINGLE	3' - 0"	HM		1		Phase 2
2nd FLOOR	212	212	Exam - Peds	3' - 0"	7' - 0"	F	SINGLE	3' - 0"	HM		1		Phase 2
2nd FLOOR	214.1	C240	Corridor	3' - 0"	7' - 0"	F	SINGLE	3' - 0"	HM		3	CARD ACCESS	Phase 2
2nd FLOOR	215	215	Toilet - Staff	3' - 0"	7' - 0"	F	SINGLE	3' - 0"					Phase 2
2nd FLOOR	216	216	Office	3' - 0"	7' - 0"	F	SINGLE	3' - 0"	HM		2		Phase 2
2nd FLOOR	217	217	Office	3' - 0"	7' - 0"	F	SINGLE	3' - 0"	HM		2		Phase 2
2nd FLOOR	218	218	Env. Svcs / Jan	6' - 0"	7' - 0"	F	PAIR	3' - 0"	HM			STOREROOM FUNCTION	Phase 2
2nd FLOOR	219	219	Shared Office	3' - 0"	7' - 0"	F	SINGLE	3' - 0"	HM		2		Phase 2
2nd FLOOR	220	220	New Patient Dept.	3' - 0"	7' - 0"	F	SINGLE	3' - 0"	HM		1		Phase 2
2nd FLOOR	242	242	Techs	3' - 0"	7' - 0"	F	SINGLE	3' - 0"	HM		3	CARD ACCESS	Phase 2
2nd FLOOR	244	244	Office	3' - 0"	7' - 0"	F	SINGLE	3' - 0"	HM		2		Phase 2
2nd FLOOR	250	250	Pentacam	3' - 6"	6' - 8"	F	SINGLE	3' - 6"	HM		1		Phase 2

DOOR HARDWARE:

1. 3 - HEAVY WEIGHT HINGES
   1 - PASSAGE SET- AL10S-SAT
   3 - DOOR SILENCERS
   1 - FLOOR STOP
2. 3 - HEAVY WEIGHT HINGES
   1 - ENTRANCE/OFFICE LOCK -AL50PD-SAT
   3 - DOOR SILENCERS
   1 - FLOOR STOP
3. 3 - HEAVY WEIGHT HINGES
   1 - CLASSROOM LOCK - AL70PD-SAT
   3 - DOOR SILENCERS
   1 - ELECTRIC STRIKE
   1 - FLOOR STOP
4. 3 - HEAVY WEIGHT HINGES
   1 - STOREROOM LOCK -AL80PD-SAT
   1 - ELECTRIC STRIKE
   3 - DOOR SILENCERS
   1 - FLOOR STOP
5. 3 - HEAVY WEIGHT HINGES
   1 - HOSPITAL PRIVACY -AL44S-SAT
   3 - DOOR SILENCERS
   1 - FLOOR STOP

Door Elevation Legend Copy 1
1/4" = 1'-0"

Door Frame Legend Copy 1
1/4" = 1'-0"

DOOR AND WINDOW NOTES

1. AT EXTERIOR WALLS AND MASONRY WALLS, COAT THE INSIDE OF ALL HOLLOW METAL FRAMES WITH BITUMINOUS COATING.

2. FILL ALL INTERIOR HOLLOW METAL FRAMES ADJACENT TO MASONRY WITH MORTAR.

3. PACK MINERAL-FIBER INSULATION IN ALL INTERIOR HOLLOW METAL FRAMES IN STUD WALLS.

4. FILL ALL EXTERIOR METAL DOOR FRAMES WITH LOW-EXPANSION SPRAY-FOAM INSULATION.

5. REFER TO SPECIFICATIONS FOR LOCATIONS OF TEMPERED, LAMINATED, WIRED, AND INSULATING GLASS.

6. AT DOOR, WINDOW AND LOUVER OPENINGS IN EXTERIOR WALLS WITH MASONRY VENEER PROVIDE METAL PAN FLASHING AT HEADS UNLESS NOTED OTHERWISE.

7. PROVIDE METAL RAIN HOOD AT ALL EXTERIOR HOLLOW METAL FRAMES.

8. PROVIDE DOOR STOPS TO PROTECT WALLS AT ALL LOCATIONS WHERE A DOOR SWING WILL STRIKE THE WALL.

9. ALL EXTERIOR DOORS SHALL HAVE WEATHER STRIPPING, THRESHOLDS, AND SHALL BE INSTALLED WEATHERTIGHT.

Door & Window General Notes
12" = 1'-0"

1 HM FRAME DETAILS @ GWB Copy 1
1 1/2" = 1'-0"

PDT ARCHITECTS
49 DARTMOUTH STREET
PORTLAND, MAINE
04101
207-775-1059
www.pdtarchs.com

COPYRIGHT
PDT Architects
Reuse or reproduction of the contents of this document is not permitted without written permission of PDT Architects.

15 Lowell Street, Portland, Maine 04101

#	Date	Description
11	12/7/17	Level 1 - TOilet 127A

Revision Schedule

REGISTERED ARCHITECT DAVID C. WEBSTER No. 923 STATE OF MAINE

JOB NO. 16064

DRWN: Author CHK: Checker

SCALE:

ISSUE: Pricing Set
November 21, 2017

TITLE: Levels 1 + 2 - Schedules, Legends & Diagrams

SHEET A601