Reviewed for Code Compliance
Inspections Division
Fire Prevention Bureau
Date: 12/08/17

FIRE ALARM SYSTEM LAYOUT – 3RD FLOOR
SCALE: 1/8" = 1'

GENERAL NOTES:
INSTALLATION SHALL COMPLY WITH NFPA 72 AND THE NATIONAL ELECTRIC CODE.
ALL WIRING SHALL BE FREE OF FAULTS (OPEN, GROUND, SHORT) PRIOR TO CONNECTING TO FIRE ALARM PANEL.
CIRCUIT BREAKER LOCK SHALL BE INSTALLED AND CIRCUIT LABELED IN RED.

SYMBOL LEGEND

ITEM NO.	SYMBOL	QTY. TOTAL	DESCRIPTION
1	○	10	STANDARD BASE (DB–11) – OCTAGON BOX
2		1	HEAT DETECTOR (HI921) – MOUNTS ON DB–11
3	I	3	LINE ISOLATOR (HLIM) – 4" SQUARE
4	DM	1	DUAL MONITOR MODULE (HTRI–D) – 4" SQUARE
5	M	3	MONITOR MODULE (HTRI–S) – 4" SQUARE
6	P	9	PULL STATION (MSM–KD/HTRI–M) – SINGLE GANG
7	RM	4	INPUT/OUTPUT MODULE (HTRI–R) – 4" SQUARE
8		9	SMOKE DETECTOR (OH921) – MOUNTS ON DB–11
9	XX	53	HORN/STROBE (2H–MC–R) – SINGLE GANG OR 4" SQUARE
10	XX	88	STROBE (2R–MC–R) – SINGLE GANG OR 4" SQUARE
11	ANN	1	ANNUNCIATOR (FT–2015)
12	FACP	1	FIRE ALARM CONTROL PANEL (FC–922)
13	NAC	3	NAC PANEL (PAD–4)

FIRE ALARM SYSTEM LAYOUT – 4TH FLOOR
SCALE: 1/8" = 1'

DEVICE ELEVATION DETAIL
NOT TO SCALE

N

1/8"=1' SCALE 2' 8' 1' 4' 16'

DATE	REVISIONS

REQUIRED APPROVALS
OWNER / ARCHITECT
STATE FIRE MARSHAL
LOCAL FIRE MARSHAL
OWNER'S INSURANCE CO.

DRAWN BY CRM

CHECKED BY

CONTRACTOR LICENSE #

MAINE EYE CARE
15 LOWELL ST PORTLAND, ME 04102

CONTRACT WITH: DEBLOIS ELECTRIC

EASTERN FIRE
FIRE PROTECTION CONTRACTORS AND ENGINEERS
www.easternfiregroup.com
Home Office
170 Kittyhawk Ave.
P.O. Box 1350
Auburn, ME 04210–1390
207–784–1507
Satellite Office
480 Harlow St.
Bangor, ME 04401
207–942–8014

FIRE ALARM SYSTEM
PLANS & DETAILS

DWG. NO.
FA-1

JOB NUMBER
1-0583-FA-17

SCALE
AS NOTED

DATE
8/24/17