

SECTION 10005

MISCELLANEOUS SPECIALTIES

1 PART 1 GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of Contract including General and Supplementary Conditions and Division 1 specification sections apply to Work of this section.

1.2 SECTION INCLUDES

- A. Fire extinguishers.
- B. Fire extinguisher cabinets.
- C. Postal specialties
- D. Closet Shelving
- E. Knox Boxes

1.3 SUBMITTALS

- A. Product Data: Provide data on Product, and accessories.
- B. Operating and Maintenance Instructions: Include relevant instructions. Include maintenance information.

1.4 QUALITY ASSURANCE

- A. Fire Extinguishers: Conform to NFPA 10.
- B. Postal Specialties: Comply with USPS requirements.

2 PART 2 PRODUCTS

2.1 FIRE EXTINGUISHERS

- A. Manufacturers:
  - 1. Allenco.
  - 2. Amerex.
  - 3. Ansul Fire Protection
  - 4. Bobrick Washroom Equipment.
  - 5. JL Industries.
  - 6. Larsen's Manufacturing Co.

7. Potter-Roemer/Div. Smith Industries Inc.
  8. Walter Kidde/Div. Kidde Inc.
- B. Multi-Purpose Dry Chemical Type: Enameled steel tank, with pressure gage, 2A:10BC rating..
  - C. Cabinets: Semi-recessed type, steel cabinet, full glass door with baked enamel finish, fire rated where installed in rated partitions.
  - D. Brackets: Manufacturer's standard surface mounted bracket for extinguishers not indicated to have a cabinet.
- 2.2 POSTAL SPECIALITES (NIC – To be provided by US Postal Service, Installed by G.C.)
- A. Manufacturers:
    1. As provided by US Postal Service.
  - B. Mailboxes: Horizontal style, pedestal mount, front loading, key locking, for exterior application, in configuration indicated.
    1. Quantity: 21 compartments (3"H x 12"W x 15"D) plus letter drop and 2 parcel boxes (15"H x 12"W x 15"D).
    2. Finish: satin anodized aluminum.
- 2.3 CLOSET SHELVING
- A. Manufacturers
    1. Clairson International/ClosetMaid
    2. Schulte Corp.
  - B. Shelving: Steel wire shelving with manufacturer's standard PVC or epoxy coating and standard installation hardware.
- 2.4 KNOX BOXES
- A. Manufacturers: Knox Co. #3200 Series Rapid Entry System

### 3 PART 3 EXECUTION

#### 3.1 EXAMINATION AND PREPARATION

- A. Verify that surfaces and internal wall blocking are ready to receive work and opening dimensions are as instructed by the manufacturer.

#### 3.2 INSTALLATION - FIRE EXTINGUISHERS

- A. Install extinguishers in accordance with manufacturer's instructions.
- B. Mount units to conform to ADA requirements, with top less than 48" above floor.

- C. Install units level and plumb in wall openings.

3.3 INSTALLATION – POSTAL SPECIALTIES

- A. Install postal specialties in accordance with USPS requirements and manufacturer's instructions.
- B. Install units level and plumb in wall openings.

3.4 INSTALLATION – CLOSET SHELVING

- A. Install shelving in accordance with manufacturer's instructions.
- B. Install units level and plumb.

3.5 INSTALLATION – KNOX BOXES

- A. Install knox boxes in accordance with manufacturer's instructions.
- B. Install units level and plumb.
- C. Install (1) one knox box per building at location as indicated if indicated on drawings. Confirm acceptability of location with authority having jurisdiction. Coordinate with Architect.

...END OF SECTION