

SECTION 10800

TOILET AND BATH ACCESSORIES

1 PART 1 GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of Contract including General and Supplementary Conditions and Division 1 specification sections apply to Work of this section.

1.2 SECTION INCLUDES

- A. Toilet and bath, shower, washroom accessories.
- B. Grab bars.

1.3 SYSTEM DESCRIPTION

- A. Conform to applicable code for installing work in conformance with ANSI A117.1 and ADA.

1.4 SUBMITTALS

- A. Product Data: Provide data on accessories describing size, finish, details of function, attachment methods.
- B. Supply 2 keys for each accessory to Owner. Key all accessories alike.

2 PART 2 PRODUCTS

2.1 MATERIALS

- A. Manufacturers: Products of one or more manufacturers are listed in Schedules to establish quality, appearance and performance characteristics. Products of other manufacturers may be accepted subject to review by Architect.
 - 1. American Specialties Inc.
 - 2. Basco.
 - 3. Bobrick Washroom Equipment Inc.
 - 4. Bradley Corp.
 - 5. Franklin Brass.
 - 6. NuTone.
 - 7. McKinney/Parker Products Co.
 - 8. Miami-Carey.
- B. Sheet Steel: ASTM A366.
- C. Stainless Steel Sheet: ASTM A167 Type 304.

- D. Tubing: ASTM A269 stainless steel.
- E. Fasteners, Screws, and Bolts: Hot dip galvanized steel, tamper-proof.

2.2 FABRICATION

- A. Form surfaces flat without distortion. Weld and grind joints smooth.
- B. Shop assemble components and package with anchors and fittings.
- C. Back paint components to prevent electrolysis.
- D. Provide steel anchor plates, adapters, and anchor components for installation.
- E. Hot dip galvanize exposed and painted ferrous metal and fastening devices.

2.3 FINISHES

- A. Anchors: Galvanize to 1.25 oz./sq yd.
- B. Ferrous Metals - Shop Primed: Pretreat and clean, spray apply one coat primer and bake.
- C. Enamel: Pretreat, one coat primer and two coats baked enamel.
- D. Chrome/Nickel Plating: ASTM B456, Type SC 2 polished finish.
- E. Stainless Steel: No. 4 satin luster finish.

3 PART 3 EXECUTION

3.1 EXAMINATION AND PREPARATION

- A. Verify exact location of accessories for installation.
- B. Deliver inserts and rough-in frames to site. Provide templates and rough-in measurements as required.

3.2 INSTALLATION

- A. Install fixtures, accessories and items in accordance with manufacturers' instructions.
- B. Install plumb and level, securely and rigidly anchored to substrate.

Continued next page...

3.3 SCHEDULE

ITEM (1)	QTY per Public Toilet Rm.	QTY per Unit Full Bathroom	QTY per Unit Half Bathroom	MANUFACTURER	MODEL NO.
Grab Bars	36"+42"	36"+42" (H.C. only)		Bobrick	B-6206.99 series
Medicine Cabinet		1	1	Bobrick	B-299
Robe Hook	1	1	1	Bobrick	B6707
Shower Curtain Rod		1		Bobrick	B6107
Stainless Steel Mirror	1			Bobrick	B-165 1836
Toilet Tissue Dispenser	1	1	1	Bobrick	B-6857
Towel Bar	1	2	1	Bobrick	B-530
Tumbler/Brush Holder		1	1	Bobrick	B-7679

1. G.C. to provide solid wood blocking in wall for all scheduled toilet accessories.
2. Provide solid wood blocking at all locations of future grab bars (by owner) in all remaining handicapped adaptable units.

...END OF SECTION