

SECTION 12511

WINDOW TREATMENT

1 PART 1 GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of Contract including General and Supplementary Conditions and Division 1 specification sections apply to Work of this section.

1.2 SECTION INCLUDES

- A. Curtain rods.
- B. Horizontal metal slat louver blinds

1.3 SUBMITTALS

- A. Product Data: Provide data indicating physical and dimensional characteristics and operating features.
- B. Samples: Submit samples for selection of color and finish of shades.

2 PART 2 PRODUCTS

2.1 CURTAIN RODS

- A. Manufacturers:
 - 1. Bali-Graber Contract.
 - 2. Kirsch.
- B. Curtain Rods: Steel C shaped track system with nylon carriers, ball bearing pulleys and polyester cord traverse operation.
- C. Accessory Hardware: Type recommended by manufacturer.

2.2 HORIZONTAL LOUVER BLINDS

- A. Manufacturers:
 - 1. Bali-Graber Contract.
 - 2. Kirsch.
 - 3. Levolor
 - 4. Hunter Douglas

- B. Blinds: Horizontal slat louvers hung from full-width headrail with full-width bottom rail; manual control of raising and lowering by cord with full range locking; blade angle adjustable by control wand.
- C. Metal Slats: Spring tempered pre-finished aluminum; radiused slat corners, with manufacturing burrs removed; perforated.
 - a. Width: 1 inch
 - b. Thickness: 0.006inch.
 - c. Color: As selected.
- D. Attachment Hardware: Type recommended by blind manufacturer.

2.3 FABRICATION

- A. Fabricate blinds to fit within openings with uniform edge clearance as recommended by manufacturer.
- B. At openings requiring multiple blind units, provide separate blind assemblies with space of 1/2 inch between assemblies, occurring at window mullion centers.

3 PART 3 EXECUTION

3.1 EXAMINATION

- A. Verify that openings are ready to receive the work.

3.2 INSTALLATION

- A. Install blinds in accordance with manufacturer's instructions.
- B. Secure in place with flush countersunk fasteners.
- C. Adjust blinds for smooth operation.

...END OF SECTION