

**SECTION 02100**

**CLEARING AND GRUBBING**

**PART 1. GENERAL**

**1.1 Related Work Specified Elsewhere**

- a. The general provisions and documents of the Contract, including General and Special Conditions, apply to the work specified in this Section.
- b. Site Earthwork - Section 02200.
- c. Site Improvements - Section 02460.
- d. Landscaping - Section 02500.

**PART 2. PRODUCTS**

**2.1 Materials**

- a. Seed for erosion control and temporary seeding - Arrostock rye applied at 2.6#/1,000 square feet.

**PART 3. EXECUTION**

**3.1 Protections**

- a. Provide temporary fences, barricades, coverings or other protections to prevent damage to existing improvements, trees or vegetation indicated on the Drawings to remain.
- b. Protect improvements on adjoining properties and on Owner's property.

**3.2 Clearing**

- a. All areas requiring clearing within the Limit of Work area, shown on the Drawings, shall be done in accordance with applicable laws and ordinances. Clear site of trees, shrubs and other vegetation, except for those indicated to be left standing or transplanted. The Contractor shall be responsible for coordinating selective removal of vegetation with the Landscape Architect.

## **Fore River Apartments**

---

### 3.3 Grubbing

- a. In areas where topsoil is to be removed or disturbed, existing grades shall be grubbed free of stumps, stones, rubbish, roots or other extraneous growth or debris.
- b. Dispose of grubblings off Owner's property. Grubbings shall not be buried on site.