

CITY OF PORTLAND
 FIRE PREVENTION BUREAU
 380 Congress Street, Portland, Maine 04101
 fireprevention@portlandmaine.gov
 (207) 874-8400

NOTICE OF VIOLATION AND ORDER TO CORRECT

MARK TARDIFF
 10 WOLCOTT ST
 PORTLAND ME 04102



December 8, 2017

Location 11 FREDERIC ST	CBL 067 K020001	Inspection Date 11/15/2017
Inspector Steven Hall	Inspection Type FP Routine Inspection	Status Failed

The City of Portland Fire Department inspected this property, and found the fire and life safety code violations listed below, which you are hereby ordered to correct. You must propose a date of completion to remedy each violation, a final date of completion, and a date of re-inspection.

You must send this form to the Fire Prevention Bureau no later than 12/30/2017.

Your failure to submit a plan of action by the date provided, or to correct any violation within the applicable time frame, may result in legal action against you, the imposition of civil penalties, and the pursuit of other legal remedies.

Violation	Proposed Date of Completion
NFPA 101- 31.3.1.1.1 VERTICAL OPENINGS NOT FIRE RATED; Vertical openings shall be enclosed or protected in accordance with Section 8.6. Hole in the ceiling above the washer/dryer 1st floor apartment	<u>1 / 31 / 18</u>
NFPA 720- 5.5.6.1 CO ALARMS REQUIRED; The performance, location, and mounting of notification appliances used to initiate or direct action, evacuation or relocation of the occupants, or for providing information to occupants or staff, shall comply with the requirements of Chapter 6. Need a hardwired photoelectric Carbon Monoxide alarm in the basement. This can be a combination unit.	IMMEDIATELY install temporary alarms where required. Your signature below indicates that temporary alarms have already been installed. 
NFPA 101- 31.3.4.5.1 SMOKE ALARMS REQUIRED; In buildings other than those equipped through out with an existing, complete automatic smoke detection system, smoke alarms shall be installed in accordance with 9.6.2.10, as modified by 31.3.4.5.2, outside every sleeping area in the immediate vicinity of the bedrooms and on all levels of the dwelling unit, including basements. Install a hardwired photoelectric smoke alarm with battery backup in the basement, This can be a combination smoke/CO alarm.	IMMEDIATELY install temporary alarms where required. Your signature below indicates that temporary alarms have already been installed. 
NFPA 1 EXCESSIVE/DISORDERLY STORAGE; Reference NFPA 1 for excessive fuel-load. Remove the storage: 2nd floor rear stairs.	<u>1 / 31 / 18</u>
NFPA 101- 8.3.4.2 60 MINUTE FIRE DOOR REQUIRED; Refer to NFPA 101- Table 8.3.4.2 that states fire door assemblies for vertical shafts (including stairways, exits, and refuse chutes) are rated and required for 1 hour. Basement door must be a 60 minute rated fire door with self-closing hardware to allow the door to self close and latch.	<u>3 / 1 / 18</u>

Violation	Proposed Date of Completion
NFPA 101- 7.5.1.1 EXIT OBSTRUCTED; Where exits are not immediately accessible from an open floor area, continuous passageways, aisles, or corridors leading directly to every exit shall be maintained and shall be arranged to provide access for each occupant to not less than two exits by separate ways of travel, unless otherwise provided in 7.5.1.1.3 and 7.5.1.1.4. 1st floor back hall - bicycle. No storage of any items is allowed in an egress stairwell or common area.	<u>1 / 31 / 18</u>
NFPA 101- 31.3.4.5.1 SMOKE ALARMS REQUIRED; In buildings other than those equipped through out with an existing, complete automatic smoke detection system, smoke alarms shall be installed in accordance with 9.6.2.10, as modified by 31.3.4.5.2, outside every sleeping area in the immediate vicinity of the bedrooms and on all levels of the dwelling unit, including basements. 1st floor back stair requires repair.	<u>3 / 1 / 18</u>
NFPA 101- 31.3.2.1.1 BOILER PROTECTION REQUIRED; The areas described in Table 31.3.2.1.1 shall be protected as indicated: Boiler and fuel-fired heater rooms serving more than a single dwelling unit (minimum separation/protection is 1 hour or sprinklers) Install a domestic sprinkler head above the gas fired water heater.	<u>3 / 1 / 18</u>
FINAL DATE OF COMPLETED VIOLATION(S)	<u> / / </u>
FIRE PREVENTION BUREAU RE-INSPECTION OF COMPLETED VIOLATION(S)	<u> / / </u>

The Bureau reserves the right to reject or modify any proposed plan of action, and may require evidence of sufficient financial and technical capacity to complete the proposed plan. Please contact the Bureau with any questions.


VIOLATOR CERTIFICATION

I agree to remedy the violations listed within the timeframes provided. If I require additional time to comply, I understand that I must contact the Fire Prevention Bureau prior to the deadline to request an extension, which is entirely within the Bureau's discretion to grant or deny.

I further understand that it is my responsibility to schedule a reinspection of my property once the violations have been remedied to do so. My failure to schedule a reinspection shall be deemed an admission that the violations have not been remedied.

If I fail to comply with this agreement, I understand that I am liable for penalties pursuant to the City of Portland Code of Ordinances §§ 1-15 and 10-25, and 30-A.M.R.S. § 4452 and may be subject to further legal action.

1 / 23 / 2018
Date



Responsible Party

Date

Responsible Party

SEEN AND AGREED

01/29/2018
Date


Fire Prevention Bureau