

ICC-ES PMG Listing
PMG-1070

Effective Date: February 1, 2012

This listing is subject to re-examination in one year.

www.icc-es-pmg.org | (800) 423-6587 | (562) 699-0543 A Subsidiary of the International Code Council®

CSI: DIVISION: 22 00 00—PLUMBING
Section: 22 13 16—Sanitary Waste and Vent Piping

Product certification system:

The ICC-ES product certification system includes testing samples taken from the market or supplier's stock, or a combination of both, to verify compliance with applicable codes and standards. The system also involves factory inspections, and assessment and surveillance of the supplier's quality system.

Product: Sure Seal - Barrier Type Floor Drain Trap Seal Protection Devices ("Device") Models SS2009, SS3000, SS3509 and SS4009

Listee: Sure Seal Manufacturing, LLC
1614 South Mildred Street, Suite 12
Tacoma, Washington 98465
www.thesureseal.com

Compliance with the following codes:

2012 and 2009 *International Plumbing Code*® (IPC)
2012 and 2009 *International Residential Code*® (IRC)
2009 *Uniform Plumbing Code*® (UPC)*

**Uniform Plumbing Code*® is a copyrighted publication of the International Association of Plumbing and Mechanical Officials

Compliance with the following standards:

ASSE 1072, Performance Requirements for Barrier Type Floor Drain Trap Seal Protection Devices, American Society of Sanitary Engineering.
LC1015, PMG Listing Criteria for Elastomeric, Normally Closed, Floor Drain Evaporation Resistant Sealing System

Identification:

The product and/or package must bear the Sure Seal Manufacturing, LLC, name, the model number and the ICC-ES PMG listing mark.

Installation:

Sure Seal trap primer alternates are to be installed in accordance with the manufacturer's instructions and the applicable code.

Models:

MODEL	Device SIZE		FLOW RATE	
	Inches	mm DN	GPM	L/M
Model SS2009	2	40	12.0	45.4
Model SS3000	3	50	34.0	128.7
Model SS3509	3½	80	73.0	276.4
Model SS4009	4	100	73.0	276.4

Listings are not to be construed as representing aesthetics or any other attributes not specifically addressed, nor are they to be construed as an endorsement of the subject of the listing or a recommendation for its use. There is no warranty by ICC Evaluation Service, LLC, express or implied, as to any finding or other matter in this listing, or as to any product covered by the listing.



Conditions of listing:

1. Sure Seal devices, recognized by this listing, are intended to serve as alternates to the code-required trap primer. They must serve a functioning trap.
2. The plumbing systems must be installed in accordance with the applicable code.
3. The "Device" must be accessible.
4. Sure Seal trap primer alternates are manufactured in Bothell, Washington, under a quality control program with annual surveillance inspections by ICC-ES PMG.

