



NOTES:

1. SEE E0.0 FOR LEGEND, ABBREVIATIONS AND GENERAL NOTES.

KEYED NOTES:

- (1) MOUNT RECEPTACLE 6" ABOVE COUNTERTOP COORDINATE WITH BACKSPLASH
- $\langle 2 \rangle$ REFRIGERATOR RECEPTACLE.
- (3) DEMO EXISTING BUILT-IN STOVE UNIT. REMOVE WIRING BACK TO SOURCE. REUSE CONDUITS FOR NEW CIRCUITS WHERE POSSIBLE.
- $\langle 4 \rangle$ remove telephone, jack and wiring located here.
- 5 FURNISH NEW RECEPTACLE WIRING FED FROM GENERATOR PANEL IN UTILITY 125.
- 6 FURNISH TV RECEPTACLE AND CATV JACK ON WALL. MOUNT 60" AFF.
- $\langle 7 \rangle$ REPLACE (6) EXISTING RECEPTACLES IN THIS AREA WITH NEW COMBINATION RECEPTACLE/USB UNITS. REWIRE TO EXISTING



65 NEWBURY STREET PORTLAND, ME 04101 207.761.9000 info@portcityarch.com WWW.PORTCITYARCH.COM

REVISIONS

Description ADDENDUM #2

ADDENDUM #3

Portland Metro

Portland, Maine

ELECTRICAL POWER & SYSTEMS PLAN

E1.0

Project Number

Date

SWIFTCURRENT

Engineering Services

10 Forest Falls Dr. Unit 4B Yarmouth, ME 04096 Tel: (207) 847-9280

Drawn by

Checked by

Scale AS NOTED

16205

JMD

TDM

September 6th, 2016

A No.

В

Date 10/17/16

10/28/16