A1 **INTERIOR WALL, 2x4**

A2 **INTERIOR PLUMBING HALF WALL, 2x6**

A3 **INTERIOR FURRING PLUMBING WALL**

NEW FLOOR ASSEMBLIES

Z5 **TYPICAL SLAB-ON-GRADE ASSEMBLY AT WALK-IN COOLER**
R-Value = 10

ROOF COVERING ASSEMBLIES

RF1 **TYPICAL ROOF COVERING ASSEMBLY**
R-Value = 27
Minimum Class C

5 WALL TYPES
SCALE: 1" = 1'-0"

PLUMBING FIXTURE SCHEDULE				
ID	Name	Manufacturer	Responsibility	Notes
DWS-1	Dishwasher	TBD By Owner	Owner Furnished, Contractor Installed	
FD-1	Floor Drain	By General Contractor, Manf: TBD	Contractor Furnished, Contractor Installed	
GRS-1	Inline Grease Trap, minimum 75 gpm capacity	Basis of Design is a Watts GI-75-K, 75 gpm, 150lb grease capacity	Contractor Furnished, Contractor Installed	Installed above floor. Verify size appropriateness with City of Portland, Contact Rachel Smith
HWH-1	Hot Water Heater, Heat Pump Type 60 Gallon	By Revision Heat, Manf: TBD	Contractor Furnished, Contractor Installed	
IMK-1	Icemaker	TBD By Owner	Owner Furnished, Contractor Installed	
MSF-1	Faucet, Wall-Mounted for Mop Sink	By General Contractor, Manf: TBD	Contractor Furnished, Contractor Installed	
MSF-1	Faucet, Wall-Mounted for Mop Sink	By General Contractor, Manf: TBD	Owner Furnished, Contractor Installed	
MSK-1	Mop Sink Base	By General Contractor, Manf: TBD	Contractor Furnished, Contractor Installed	
SNK-1	Sink, Prep	TBD By Owner	Owner Furnished, Contractor Installed	Faucets and Fitting also provided by Owner
SNK-2	Sink, Handwashing	TBD By Owner	Owner Furnished, Contractor Installed	Faucets and Fitting also provided by Owner
SNK-3	Sink, 3 Bay	TBD By Owner	Owner Furnished, Contractor Installed	Faucets and Fitting also provided by Owner

KITCHEN EQUIPMENT SCHEDULE				
ID	Name	Manufacturer	Responsibility	Notes
FRZ-1	Freezer, 72" Wide	TBD By Owner	Owner Furnished, Contractor Installed	
IBN-1	Ice Bin (Below Ice Maker)	TBD By Owner	Owner Furnished, Contractor Installed	
REF-1	Refrigerator, 72" Wide	TBD By Owner	Owner Furnished, Contractor Installed	

2 PREP KITCHEN INTERIOR ELEVATION
SCALE: 3/4" = 1'-0"

1 PROPOSED EQUIPMENT PLAN ENLARGEMENT
SCALE: 1/2" = 1'-0"

CALEB JOHNSON
110 EXCHANGE ST, 2ND FLOOR, PORTL
T: 207.283.8777

LICENSED ARCHITECT
CALEB M. JOHNSON
No. ARC4209
STATE OF MAINE

Reviewed for Code Compliance
Department Review
Approved with Conditions
Date: 01/08/18

CHANGES THIS ISSUE:

ID	DESCRIPTION
CH-01	Door Opening Clarification

CODE NUMBER
A-102
SHEET NUMBER

SUBMISSIONS:

CODE	DATE	DESCRIPTION
01	11/16/2017	for Permit
02	12/6/17	95% For Construction
03	12/15/17	City Comments

DRAFTSPERSON: Patrick Boothe, AIA
DATE OF ISSUE: 11/16/2017
PROJECT STATUS: Construction Docs

Mainely Burgers Food Truck Co-op
Mainely Burgers
108 S1 John Street Portland ME 04101

95% FOR CONSTRUCTION

PROPOSED EQUIPMENT PLAN ENLARGEMENT

A-102

/Volumes/Network Files/CJAB/PROJECTS/B COMMERCIAL STUDIO/1 Current Projects/17-C-020_Mainely Burgers/1 DESIGN/DRAWINGS/Mainely Burger_Current_Permit2.pln