3D VIEW OF EXTERIOR FRONT

3D VIEW OF EXTERIOR SIDE

1 NORTH ELEVATION (FRONT)
SCALE: 1/4" = 1'-0"

2 EAST ELEVATION
SCALE: 1/4" = 1'-0"

3 SOUTH ELEVATION
SCALE: 1/4" = 1'-0"

4 WEST ELEVATION
SCALE: 1/4" = 1'-0"

WINDOW SCHEDULE

ID	# Of	Type	Size		Rough Opening Height	Sill	Manufacturer	Frame Material	Interior Finsh Material/Color	Exterior Finish Material/ Color	Notes
			Width	Height							
W1	1	Storefront	10'-0"	6'-7 1/2"	7'-3 1/2"	0'-8"	Kawneer Trifab VG 451 (Basis of Design) or equal	Alum	Black, Anodized	Black	VIF rough opening size
W2	1	Storefront	10'-2 1/2"	6'-8"	7'-4"	0'-8"	Kawneer Trifab VG 451 (Basis of Design) or equal	Alum	Black, Anodized	Black	VIF rough opening size
W3	1	Storefront	4'-0"	5'-5"	9'-11 1/2"	4'-6 1/2"	Kawneer Trifab VG 451 (Basis of Design)	Alum	Black, Anodized	Black	VIF rough opening size
	3										

DOOR SCHEDULE

Location	Element ID	Type	Nom. Size	Position	Material	Manufacturer	Door Finish	Glazing	Hdw Set	Hdw Finish	Notes
1ST FLR	101	Storefront Door	3'-0"×7'-4"	Exterior	Aluminium	Same manufacturer as adjacent	Black	Yes	By Manf	Satin Nickel	ADA compliant, provide ADA compliant hardware and closer
1ST FLR	WIC	Walk-In Cooler Door (Intergral)	2'-6"×6'-8"	Interior	Insulated	By Walk-in Cooler Manfacturer	NA	No	By Manf.	By Manf	

Door and Window Notes:
1. Glazing to meet minimum U-factor requirement (0.35) for climate zone 6A per 2009 IECC table 502.3.
2. Verify RO's with selected manufacturer and coordinate with floor plan and framing.
3. Contractor to provide shop drawings for Architect's Review

WINDOW ELEVATIONS (1/4" = 1'-0")

ID	W1	W2	W3
Elevation (Nominal Dims)			
Window Type	Storefront	Storefront	Storefront

DOOR ELEVATIONS (1/4" = 1'-0")

ID	101	WIC
Elevation View		
Tag (Attributes)	Storefront Door	Walk-In Cooler Door (Intergral)

PERMIT SET

CALEB JOHNSON
110 EXCHANGE ST, 2ND FLOOR, PORTL
T: 207.283.8777

Reviewed for Code Compliance
Inspection Division
Department of Building Safety
Date: 01/08/18

LICENSED ARCHITECT
CALEB M. JOHNSON
No. ARC4209
STATE OF MAINE

DRAFTSPERSON: Patrick Boothe, AIA
DATE OF ISSUE: 10/16/17
PROJECT STATUS: PreDesign

Mainely Burgers Food Truck Co-op

Mainely Burgers
108 St John Street Portland ME 04101

PROPOSED ELEVATIONS & SCHEDULES

A-201

/Volumes/Network Files/CJAB/PROJECTS/B COMMERCIAL STUDIO/1 Current Projects/17-C-020_Mainely Burgers/1 DESIGN/DRAWINGS/Mainely Burger_Current_Permit.pln