

## LINE ITEM QUOTES


The following is a schedule of the windows and doors for this project. For additional unit details, please see Line Item Quotes. See shop drawings for review. Wood tilt pacs may require trimming and shimming for tight fit into existing window frames as needed.

Line #2	Mark Unit: Tilt Pac Windows
Qty: 2	



Marvin Wood Round Top  
 RT-2, TILT PAC SINGLE HUNG  
 Sash Opening  
 33 5/8" X 58"  
 Primed Pine Ext Finish  
 Primed Pine Int Finish  
 IG 3/4 in  
 Low E1 w/Argon  
 SDL 7/8" WITH SPACER BAR 5-RAD. 3W2H/3W2H  
 BRASS SASH LOCK  
 WHITE JAMB HARDWARE  
 UNEQUAL SASH, PER SKETCH  
 PUTTY EXTERIOR GLAZING BEAD & SDL  
 2 3/4" BOTTOM RAIL  
 SPC 10-DEGREE BEVEL  
 SEE ATTACHED CAD DRAWING / MAKE TO SASH OPENING GIVEN  
 \*\*\*Note: ETO: Non-System Generated Pricing

Line #3	Mark Unit: Single Hung Tilt Pac
Qty: 3	



As Viewed From The Exterior  
 SO 25 3/4" X 36 1/2"

Primed Pine Exterior  
 Primed Pine Interior  
 Wood Double Hung Tilt Pac  
 Sash Opening 25 3/4" X 36 1/2"  
 #SINGLE HUNG  
 Cottage 1.0:3.0  
 Top Sash  
 Primed Pine Sash Exterior  
 Primed Pine Sash Interior  
 G.S. 21 3/4" X 10 11/64"  
 IG  
 Low E2 w/Argon  
 Stainless Perimeter and Spacer Bar  
 7/8" SDL - With Spacer Bar - Stainless  
 Rectangular - Special Cut 3W1H  
 Primed Pine Ext - Primed Pine Int  
 Putty Exterior Glazing Profile  
 Bottom Sash  
 Primed Pine Sash Exterior  
 Primed Pine Sash Interior  
 G.S. 21 3/4" X 20 21/64"  
 IG  
 Low E2 w/Argon  
 Stainless Perimeter and Spacer Bar  
 7/8" SDL - With Spacer Bar - Stainless  
 Rectangular - Special Cut 3W2H  
 Primed Pine Ext - Primed Pine Int  
 Putty Exterior Glazing Profile  
 #Add to make Low E I with Argon  
 1 /Unit Brass Sash Lock  
 White Jamb Hardware  
 Special Bevel - 10 Degrees  
 No Screen  
 # Non system generated Pricing