



## Submittal Data Sheet

0.75-Ton Wall Mounted Unit

CTXS09HVJU

### FEATURES

- Connects with multi-split systems
- Intelligent eye occupancy sensor
- Vertical and horizontal auto swing
- Hot start technology
- 12 year limited parts and compressor warranty with online registration

### BENEFITS

- Low ambient heat operation down to 0° F
- LCD wireless remote with backlit display





## Submittal Data Sheet

0.75-Ton Wall Mounted Unit

CTXS09HVJU

### PERFORMANCE

Indoor Unit Model No.	CTXS09HVJU	Indoor Unit Name:	0.75-Ton Wall Mounted Unit
Type:	Wall Mounted	Rated Cooling Conditions:	Indoor (°F DB/WB): 80 / 67 Ambient (°F DB/WB): 95 / 75
Rated Cooling Capacity (Btu/hr):	8,500	Rated Heating Conditions:	Indoor (°F DB/WB): 70 / 70 Ambient (°F DB/WB): 47 / 43
Sensible Capacity (Btu/hr):		Rated Piping Length(ft):	
Cooling Input Power (kW):	0.040	Rated Height Separation (ft):	
Rated Heating Capacity (Btu/hr):	10,000		
Heating Input Power (kW):	0.05		

### INDOOR UNIT DETAILS

Power Supply (V/Hz/Ph):	208-230 / 60 / 1	Airflow Rate (H/M/L) (CFM):	388/335/283
Power Supply Connections:	L1, L2, Ground	Moisture Removal (Gal/hr):	
Min. Circuit Amps MCA (A):		Gas Pipe Connection (inch):	3/8
Max Overcurrent Protection (MOP) (A):		Liquid Pipe Connection (inch):	1/4
Dimensions (HxWxD) (in):	11-7/16 x 31-5/16 x 9-3/8	Condensate Connection (inch):	11/16
Panel (HxWxD) (in):		Sound Pressure (H/M/L) (dBA):	44/40/35
Net Weight (lb):	20	Sound Power Level (dBA):	
Panel Weight (lb):		Ext. Static Pressure (Rated/Max) (inWg):	0.00 / 0.00

**Submittal Data Sheet**  
 0.75-Ton Wall Mounted Unit  
 CTXS09HVJU

**DIMENSIONAL DRAWING**

THE MARK ( \* ) SHOWS PIPING DIRECTION

