Inspections Division
Date: 12/30/13

# FINISH SCHEDULE

| ROOM # | ROOM NAME | FLOOR | BASE | WALL | CEILING | NOTES |
|---|---|---|---|---|---|---|
| 101 | OFFICE | CARPET TILE #2 | PTD. WOOD | PTD. GYP | EXISTING | |
| 102 | OFFICE | CARPET TILE #2 | PTD. WOOD | PTD. GYP | EXISTING | |
| 103 | OFFICE | CARPET TILE #2 | PTD. WOOD | PTD. GYP | EXISTING | |
| 104 | CORRIDOR | CARPET TILE #1 | PTD. WOOD | PTD. GYP | EXISTING | |
| 105 | CONF. ROOM | CARPET TILE #3 | PTD. WOOD | PTD. GYP | EXISTING | |
| 106 | FILES | CARPET TILE #1 | PTD. WOOD | PTD. GYP | EXISTING | |
| 107 | RESTROOM | CERAMIC TILE | PTD. WOOD | PTD. GYP | EXISTING | |
| 108 | STORAGE | CARPET TILE #1 | PTD. WOOD | PTD. GYP | EXISTING | |
| 109 | KITCHEN | CERAMIC TILE | PTD. WOOD | PTD. GYP | EXISTING | |
| 110 | CORRIDOR | CERAMIC TILE | PTD. WOOD | PTD. GYP | EXISTING | |
| 111 | VESTIBULE | CERAMIC TILE | PTD. WOOD | PTD. GYP | EXISTING | |
| 112 | LOBBY | CARPET TILE #1 | PTD. WOOD | PTD. GYP | EXISTING | |
| 113 | RECEPTION | CARPET TILE #1 | PTD. WOOD | PTD. GYP | EXISTING | |
| 114 | PLAN ROOM | CARPET TILE #1 | PTD. WOOD | PTD. GYP | EXISTING | |
| 115 | OFFICE | CARPET TILE #2 | PTD. WOOD | PTD. GYP | EXISTING | |
| 116 | CORRIDOR | CARPET TILE #1 | PTD. WOOD | PTD. GYP | EXISTING | |
| 117 | BATHROOM | CERAMIC TILE | PTD. WOOD | PTD. GYP | EXISTING | |
| 118 | MEETING | CARPET TILE #3 | PTD. WOOD | PTD. GYP | EXISTING | |
| 119 | OFFICE | CARPET TILE #2 | PTD. WOOD | PTD. GYP | EXISTING | |
| 201 | OFFICE | CARPET TILE #2 | PTD. WOOD | PTD. GYP | EXISTING | |
| 202 | OFFICE | CARPET TILE #2 | PTD. WOOD | PTD. GYP | EXISTING | |
| 203 | CORRIDOR | CARPET TILE #1 | PTD. WOOD | PTD. GYP | EXISTING | |
| 204 | BATHROOM | CERAMIC TILE | PTD. WOOD | PTD. GYP | EXISTING | |
| 205 | OFFICE | CARPET TILE #2 | PTD. WOOD | PTD. GYP | EXISTING | |
| 206 | OFFICE | CARPET TILE #2 | PTD. WOOD | PTD. GYP | EXISTING | |
| ST1 | STAIR | CARPET RUNNER | -- | PTD. GYP | EXISTING | FIX MISSING PORTION OF CEILING |
| ST2 | STAIR | EXISTING | -- | PTD. GYP | EXISTING | |

# DOOR SCHEDULE

| DOOR | SIZE | DOOR | | | | FRAME | | |
|---|---|---|---|---|---|---|---|---|
| NO. | W x H x T | TYPE | MATERIAL | FINISH | THRESH | MATERIAL | FINISH | NOTES |
| 01 | 3'-0" x 7'-0" x 1 3/4" | A | SCW | PTD | - | WD | PDT | |
| 02 | 3'-0" x 7'-0" x 1 3/4" | B | SCW | PTD | - | WD | PDT | |
| 03 | 3'-0" x 7'-0" x 1 3/4" | A | SCW | PTD | - | WD | PDT | |
| 04 | 3'-0" x 7'-0" x 1 3/4" | A | SCW | PTD | - | WD | PDT | |
| 05 | 3'-0" x 7'-0" x 1 3/4" | A | SCW | PTD | - | WD | PDT | PANIC HARDWARE |
| 06 | NO DOOR | | | | | | | |
| 07 | EXISTING | | | | | | | |
| 08 | 3'-0" x 7'-0" x 1 3/4" | A | SCW | PTD | - | WD | PDT | |
| 09 | 3'-0" x 7'-0" x 1 3/4" | A | SCW | PTD | - | WD | PDT | |
| 10 | 3'-0" x 7'-0" x 1 3/4" | A | SCW | PTD | - | WD | PDT | |
| 11 | 3'-0" x 7'-0" x 1 3/4" | B | SCW | PTD | - | WD | PDT | |
| 12 | 5'-0" x 7'-0" x 1 3/4" | D | SCW | PTD | WD | WD | PDT | REPLICATE EXISTING |
| 13 | 5'-0" x 7'-0" x 1 3/4" | C | SCW | PTD | - | WD | PDT | |
| 14 | 3'-0" x 7'-0" x 1 3/4" | B | SCW | PTD | - | WD | PDT | |
| 15 | 3'-0" x 7'-0" x 1 3/4" | B | SCW | PTD | - | WD | PDT | |
| 16 | 3'-0" x 7'-0" x 1 3/4" | B | FIBERGLASS | | ALUM. | HM | PDT | EXTERIOR DOOR |
| 17 | 3'-0" x 7'-0" x 1 3/4" | B | SCW | PTD | - | WD | PDT | |
| 18 | 3'-0" x 7'-0" x 1 3/4" | A | SCW | PTD | - | WD | PDT | |
| 19 | 3'-0" x 7'-0" x 1 3/4" | B | SCW | PTD | - | WD | PDT | |
| 20 | 3'-0" x 7'-0" x 1 3/4" | A | SCW | PTD | - | WD | PDT | |
| 21 | EXISTING | | | | | | | |
| 22 | RELOCATE EXISTING DOOR AND FRAME | | | | | | | |
| 23 | EXISTING | | | | | | | |
| 24 | RELOCATE EXISTING DOOR AND FRAME | | | | | | | |
| 25 | EXISTING | | | | | | | |
| 26 | EXISTING | | | | | | | |

# DOOR TYPES

TYPE A
1 3/4" SOLID CORE
PAINT GRADE WOOD

TYPE B
FULL LITE
PAINT GRADE WOOD

TYPE C
FULL LITE
PAINT GRADE WOOD

TYPE D
EXT. WOOD DOOR
REPLICATE EXISTING

# FINISH KEY

| | |
|---|---|
| CERAMIC TILE- | Dal Tile "Ayers Rock" 13" x 20" |
| CARPET TILE #1- | Mannington "Micro Strie" |
| CARPET TILE #2- | Shaw "Tru Colors" |
| CARPET TILE #3- | Mannington "Bark" |
| VCT- | Mannington "Solid Point" |
| CARPET RUNNER | Mannington "Typeset" |

1 KITCHEN 109 ELEVATION
SCALE: 1/2"=1'-0"

2 GLASS WALL ELEVATION
SCALE: 1/2"=1'-0"

3 GLASS WALL ELEVATION
SCALE: 1/2"=1'-0"

7 DRAWING STORAGE ELEVATION
SCALE: 1/2"=1'-0"

8 SHELVING ELEVATION
SCALE: 1/2"=1'-0"

W1 TYPICAL UNRATED INTERIOR PARTITION

W1 UNRATED OFFICE PARTITION WALL ASSEMBLY.

1. **Floor and Ceiling Runners —** Channel shaped, attached to floor and ceiling in two rows, a min 1 in. apart, with steel fasteners spaced 24 in. OC. Runners fabricated from min No. 25 MSG galv steel, 1-1/4 in. deep and 3-5/8 in. wide. Use 6 in. wide runners at plumbing walls.
2. **Steel Studs —** Channel shaped, supplied with cutouts, friction -fitted into floor and ceiling runners and spaced a max 24 in. OC. Studs cut 1/2 in. less than assembly height and evenly staggered between the two rows of floor and ceiling runners. Studs fabricated from min No. 25 MSG galv steel, min 3-5/8 in. wide by 1-5/8 in. deep with 5/8 in. folded back return flange legs. Use 6 in. wide studs in plumbing walls.
3. **Gypsum Board –** 5/8 in. thick, 4 ft wide, attached to wood studs with Type S steel screws spaced 8 in. OC. along edges of board and 12 in. OC in the field of the board. Joints oriented vertically and staggered on opposite sides of the assembly. 48 in. OC.
4. Roxul insulation - 3" minimum
5. **Joint Tape and Compound –** Vinyl, dry or premixed joint compound, applied in two coats to joints and screw heads; paper tape, 2 in. wide, embedded in first layer of compound over all joints. As an alternate, nominal 3/32 in. thick gypsum veneer plaster may be applied to the entire surface of Classified veneer baseboard. Joints reinforced. Paper tape and joint compound may be omitted when gypsum boards are supplied with square edges.

9 SHELVING DETAIL
SCALE: 3"=1'-0"

5 TYPICAL BASE
SCALE: 3"=1'-0"

4 TYPICAL DOOR TRIM DETAILS
SCALE: 3"=1'-0"

6 GLASS WALL DETAIL
SCALE: 3"=1'-0"

LICENSED ARCHITECT
DAVID LLOYD
NO. 936
STATE OF MAINE

ARCHETYPE, P.A.
ARCHITECTS
48 Union Wharf Portland, Maine 04101
(207) 772-6022 Fax (207) 772-4056

Project:
501 DANFORTH STREET
PORTLAND, ME

Scale 1/4" = 1'-0"

Date Dec. 9th, 2013
Revisions:

SCHEDULES, INTERIOR ELEVATIONS & DETAILS

A-3