1 3rd Floor Section
Scale: 1/4" = 1'-0"

Door Schedule

Door Tag		Nominal Size Width	Height	Rating	Comments
D-	X	3'0"	6'8"		REMOVE EXISTING DOOR & FRAME
D-	X	2'6"	6'8"		REMOVE EXISTING DOOR & FRAME
D-	X	2'6"	6'8"		REMOVE EXISTING DOOR & FRAME
D-	X	2'6"	6'8"		REMOVE EXISTING DOOR & FRAME
D-	X	2'6"	6'8"		REMOVE EXISTING DOOR & FRAME
D-	X	3'0"	6'8"		REMOVE EXISTING DOOR & FRAME
D1-	1	2'8"	6'8"		SELF-CLOSING HINGES, EXIST. DOOR
D1-	2	2'6"	6'8"	60 MN	SELF-CLOSING HINGES
D2-	1	2'8"	6'8"	60 MIN	SELF-CLOSING HINGES
D2-	2	2'8"	6'8"	60 MIN	SELF-CLOSING HINGES
D2-	3	2'8"	6'8"	60 MIN	SELF-CLOSING HINGES
D2-	4	2'6"	6'8"	60 MIN	SELF-CLOSING HINGES
D2-	5	2'8"	6'8"	60 MIN	SELF-CLOSING HINGES
D3-	1	2'6"	6'8"		
D3-	2	2'8"	6'8"		INSULATED DOOR, FULL LITE
D3-	3	2'8"	6'8"	60 MIN	SELF-CLOSING HINGES
D3-	4	2'6"	6'8"		
D3-	5	2'6"	6'8"		

RESURGAM, CITY OF PORTLAND, MAINE
Reviewed for Code Compliance
Inspections Division
Approved with Conditions
Date: 02/13/14

Window Schedule with Images

Image	Mark	Nominal Size O.A. Width	O.A. Height	Sash Operation	Openings RO Width	RO Height	Comments
	A3	6'6"	3'6"	Custom	6'6 1/2"	3'6 1/2"	HORIZONTAL MUNTIN DEPTH TO MATCH EXISTING DH MEETING RAIL
	B	2'4"	5'0"	Double Hung	2'4 1/2"	5'0 1/2"	SIZED TO MATCH ORIGINAL WINDOWS, V.I.F.

Interior Renovations for
Feddersen Residence
Portland, Maine
481 Danforth Street CBL 71/A/1

Residential Design Studio, LLC
Carol A. Morrissette
174 Danforth Street
Portland, Maine 04102
T 207.699.4184
C 207.671.7965

A6
hp revision 2
bp #01283
11/8/13