
12. CONSTRUCTION MANAGEMENT PLAN

The construction work for the project will be completed by Cianbro, the Applicant. The project site will be managed during construction to minimize impacts to the surrounding area and natural resources. The construction area is internal to the property which is currently utilized for construction equipment and material storage, and existing site security features will be maintained. No traffic or pedestrian controls are anticipated to be required.

Temporary erosion and sedimentation control measures will be established prior to the start of construction and removed after construction has been completed and the site has been stabilized. Erosion and sedimentation control measures will include silt fencing and floating turbidity curtains.

Appendix E includes an erosion control plan and Appendix G includes a construction sequencing plan and schedule.