

## SECTION 10800 – TOILET AND BATH ACCESSORIES

### PART 1 - GENERAL

#### 1.1 DESCRIPTION

A. Furnish and install the following items:

1. Grab bars
2. Mirrors
3. Double robe hook
4. Mop holder and shelf
5. Infant-care products
6. Waste receptacles
7. Utility shelf
8. Folding shower seats
9. Toilet seat cover dispenser
10. Sanitary napkin disposal
11. Toilet Tissue Dispenser with hoods

B. Refer to Section 10900 for Owner-provided accessories requiring blocking and support in walls.

#### 1.2 SUBMITTALS

A. Product Data: For each product indicated.

B. Product Schedule: Indicating types, quantities, sizes, and installation locations by room of each accessory required. Use room and product designations indicated on Drawings.

#### 1.3 WARRANTY

A. Special Mirror Warranty: Manufacturer's standard form in which manufacturer agrees to repair or replace mirrors that develop visible silver spoilage defects within 15 years from date of Substantial Completion.

### PART 2 - PRODUCTS

#### 2.1 MANUFACTURERS

A. Bobrick Washroom Equipment or equal.

B. Catalog numbers are models manufactured by Bobrick Washroom Equipment, unless otherwise indicated, provided as a standard.

1. Products specified in following Schedule of Toilet Accessories represent type, style, and quality required for this Project.

## 2.2 PRODUCTS

- A. AISI Type 302/304 stainless steel, 22 gage (.034 inch) thickness, satin finish, except where otherwise indicated.
- B. Mirror glass: 0.23 inch thickness, ASTM C 1036, Type I, Class 1, Quality No. 1, with silvering, electroplated copper coating, and protective organic coating.
- C. Fasteners: Steel screws, bolts, and other devices as required; galvanized where concealed.

## 2.3 SCHEDULE OF TOILET ACCESSORIES

- A. Units listed below are identified by BOBRICK catalog numbers unless stated otherwise.
- B. Grab Bars:
  1. Grab bar and concealed mounting plates shall be constructed of type-304 stainless steel with satin finish with peened gripping surface. Grab bar shall have wall thickness of 18-gauge and outside diameter of 1-1/4". Distance from inside of grab bar to finished wall shall be 1-1/2". Flanges shall be 1/8" thick stainless steel plate, 2"x3-1/8" in diameter, and each shall have two screw holes. Flange covers shall be 22-gauge and shall snap over mounting flanges to conceal mounting screws. Grab bar shall have 90° return to flange. Ends of grab bar shall pass through flanges and be heliarc welded to form one structural unit. Manufacturer's service and parts manual shall be provided to building owner/manager upon completion of project.
  2. BOBRICK B-5806 Series.
    - a. Horizontal mounting: B-5806.99 x 36 and 42 inches long.
- C. Tilt Mirror:
  1. Frame shall be one piece roll formed 3/4 x 3/4 inch heavy gage, Type 304 stainless steel angles with satin finish. Provide concealed wall hanger for theft-proof mounting. Corner shall be welded, ground and polished smooth.
  2. Mirror shall be 1/4-inch polished plate glass, electrologically cooper plated. Mirror shall be warranted against silver spoilage for a minimum 15 years. Protect back of mirror with 1/4-inch polystyrene padding and 20 gage galvanized steel back attached to frame with concealed screws.
  3. BOBRICK B293, 24" x 36 " (u.o.n.)
- D. Mirror:

1. Frame shall be one piece roll formed  $\frac{3}{4}$  x  $\frac{3}{4}$  inch heavy gage, Type 304 stainless steel angles with satin finish. Provide concealed wall hanger for theft-proof mounting. Corner shall be welded, ground and polished smooth.
  2. Mirror shall be  $\frac{1}{4}$ -inch polished plate glass, electrologically cooper plated. Mirror shall be warranted against silver spoilage for a minimum 15 years. Protect back of mirror with  $\frac{1}{4}$  inch polystyrene padding and 20 gage galvanized steel back attached to frame with concealed screws.
  3. BOBRICK B-290 series. Size: 24 x 36 u.o.n.
- E. Oval Mirror:
1. Bellacor No. 76638
- F. Double Robe Hook:
1. Hook and flange shall be 18-8 Type 304 heavy gage stainless steel satin finish.
  2. BOBRICK B-6727.
- G. Mop Holder and Shelf, Surface Mounted:
1. Shelf shall be 18-8 Type 304, 18-gage stainless steel with satin finish, 8 inches deep.
  2. Mop holders shall be spring loaded rubber cam with plated steel retainers, quantity standard with length specified.
  3. Rag hooks shall be 1808 Type 304, 16 gage stainless steel with satin finish.
  4. Drying rod shall be 18-8 Type 304,  $\frac{1}{4}$  inch stainless steel with satin finish.
  5. BOBRICK B-239 X 34 inch for mop holder/shelf unit; shelf unit shall be B-295 x 24 inch.
  6. Provide one each of mop holder/shelf and shelf only unit in each Janitor's Closet.
- H. Infant Changing Station:
1. Unit shall be high-impact polyethylene.
  2. BOBRICK KB-100-00.
- I. Waste Receptacle:
1. BOBRICK B-279.
- J. Folding Shower Seats:
1. BOBRICK B-517/B-518.
- K. Toilet Seat Cover Dispenser:
1. BOBRICK B-221.
- L. Sanitary Napkin Disposal:
1. BOBRICK B-254.

- M. Utility Shelf:
  - 1. BOBRICK B295-24.
- N. Soap Dispenser - Provided by Owner. (See Section 11900.)
- O. Paper Towel Dispenser – Provided by Owner. (See Section 11900.)
- P. Toilet Paper Dispenser – Provided by Owner. (See Section 11900.)
- Q. Toilet Paper Dispenser (for patient toilet rooms with integral showers)
  - 1. BoBrick B-69997.

### PART 3 - EXECUTION

#### 3.1 INSTALLATION

- A. Install accessories using fasteners appropriate to substrate indicated and recommended by unit manufacturer. Install units level, plumb, and firmly anchored in locations and at heights indicated.
  - 1. Install grab bars to withstand a downward load of at least 250 lbf, when tested according to method in ASTM F 446.
- B. Adjust accessories for unencumbered, smooth operation and verify that mechanisms function properly. Replace damaged or defective items. Remove temporary labels and protective coatings.

END OF SECTION 10800