J14	SIDELIGHT HEAD
1 1/2" = 1'-0"	AE601

G14	SIDELIGHT JAMB
1 1/2" = 1'-0"	AE601

E14	DOOR HEADER DETAIL
1 1/2" = 1'-0"	AE601

C14	DOOR JAMB DETAIL
1 1/2" = 1'-0"	AE601

FINISH SCHEDULE NOTES:

1. REFER TO FLOOR PLANS, WALL TAGS AND WALL LEGEND FOR WALL TYPE DEFINITIONS.
2. REFER TO PARTITION LEGEND FOR TYPE OF GWB COMPOSITION REQUIRED. ABUSE RESISTANT, MOISTURE RESISTANT OR OTHER TYPICAL.
3. ALL WALLS TO BE PAINTED W/ PTD-1 UNLESS NOTED OTHERWISE.

FINISH ABBREVIATIONS:

ACT1	ACOUSTICAL CEILING TILE & GRID SYSTEM
BOS	BOTTOM OF STRUCTURE
CMU	CONCRETE MASONRY UNIT, EPOXY PAINTED
CPT	CARPET
CT	CERAMIC TILE
EPTD	EPOXY PAINTED
EXP	EXPOSED STRUCTURE
GWB1	GYPSUM WALL BOARD, EPOXY PAINTED
GWB2	GYPSUM WALL BOARD, PAINTED
PTD	PAINTED
RB	RESILIENT BASE
VCT	VINYL COMPOSITION TILE

FINISH MATERIALS:

ACT-1: ARMSTRONG, 2x2 DUNE 1774 HUMIGUARD, SQUARE LAY IN CEILING, 15/16" METAL GRID SYSTEM.

PTD-1: (FIELD) SHERWIN WILLIAMS, COLOR: TBD.
PTD-2: (TRIM) SHERWIN WILLIAMS, COLOR: TBD
PTD-3: (CEILING) SHERWIN WILLIAMS, EXTRA WHITE SW7006.

RB-1: JOHNSONITE 4-INCH COVE WALL BASE, COLOR: TBD.

RUB-1: JOHNSONITE MICROTONE SPECKLED RUBBER TILE, SIZE: 24x24, SURFACE TEXTURE: HAMMERED, COLOR: TBD.

SV-1: MANNINGTON COMMERCIAL, REALITIES MAPLE GROVE, COLOR: TBD.

DOOR HARDWARE SETS

HWS-1: HINGES, LEVER STYLE LOCKSET, PUSH BUTTON ACCESS, WALL STOP, SILENCERS

HWS-2: HINGES, LEVER STYLE LOCKSET, PUSH BUTTON ACCESS, CLOSER, WALL STOP, SILENCERS

HWS-3: HINGES, LEVER STYLE LOCKSET, CARD READER, CLOSER, WALL STOP, SILENCERS.

DOOR ABBREVIATIONS

AL/ALUM	ALUMINUM
CL	CHAIN LINK
HM	HOLLOW METAL
HWS	HARDWARE SCHEDULE
INS	INSULATED
S/S	STAINLESS STEEL
STL	STEEL SHEET OR PLATE DOOR
TEMP	TEMPERED GLASS
WD	COMMERCIAL GRADE WOOD DOOR
WIRE	WIRE GLASS
SM	SECURITY MESH
Y	INDICATES YELLOW FILM ON GLASS

ROOM FINISH SCHEDULE

ROOM NUMBER	ROOM NAME	FLOOR	BASE	WALLS				CEILING	ROOM NUMBER	REMARKS
				NORTH	SOUTH	EAST	WEST	MATERIAL		
101	PHARMACY	RUB-1	RB-1	PTD-1	PTD-1	PTD-1	PTD-1	ACT-1	101	–
102	STORAGE	SV-1	RB-1	PTD-1	PTD-1	PTD-1	PTD-1	ACT-1	102	–
103	CORRIDOR	RUB-1	RB-1	PTD-1	PTD-1	PTD-1	PTD-1	ACT-1	103	–
104	CONSULTATION	SV-1	RB-1	PTD-1	PTD-1	PTD-1	PTD-1	ACT-1	104	–
105	BATHROOM	RUB-1	RB-1	PTD-1	PTD-1	PTD-1	PTD-1	ACT-1	105	–

DOOR SCHEDULE

DOOR NUMBER	DOOR			GLAZING	FRAME				HWS	FIRE RATING (MIN.)	DOOR NUMBER	REMARKS
	SIZE	MATERIAL	ELEVATION		MATERIAL	ELEVATION	HEAD	JAMB				
101	3'-6"x7'-0"	ALUM	FG	TEMP	ALUM	–	–	–	ALUM*	–	101	*HARDWARE BY FRAME MANUFACTURER, CARD READER ON EXTERIOR
102	3'-0"x7'-0"	WD	F	–	HM	1	E14	C14	HWS-2	–	102	–
103	3'-6"x7'-0"	WD	FG	TEMP	HM	2	E14	C14	HWS-3	–	103	–
104	3'-0"x7'-0"	WD	FG	TEMP	HM	1	E14	C14	HWS-1	–	104	–
105	3'-0"x7'-0"	WD	F	–	HM	1	E14	C14	HWS-1	–	105	–

GENERAL NOTES:

1. SEE GI001 FOR GENERAL PROJECT NOTES.

DOOR NOTES

1. SEE TITLE SHEET G001 FOR STANDARD ABBREVIATIONS.
2. ALL SWINGING DOORS TO BE 1-3/4" THICK (U.N.O.). BLAST RESISTANT DOOR THICKNESS PER MANUFACTURER.
3. ALL DOORS SHALL BE 3/4" UNDERCUT (TYPICAL) EXCEPT WHEN THERE IS A BOTTOM FRAME OR SILL THRESHOLD OR SPECIFICALLY NOTED OTHERWISE. ALL DOORS WITH BOTTOM FRAMES OR SILL THRESHOLDS SHALL HAVE MANUFACTURERS RECOMMENDED STANDARD UNDERCUT.
4. GLAZING NOTED ON DOOR SCHEDULE IS FOR THE DOOR AND SIDELIGHTS IN THE FRAME (TYPICAL). ALL GLAZING IN DOORS AND SIDELIGHTS TO BE SAFETY RATED CLASS I IN ACCORDANCE W/ CPSC16 CFR 1201.
5. PAINT ALL NEW DOOR FRAMES PTD-2 (SEE FINISH MATERIAL).
6. FINISH ALL WOOD DOORS TO MATCH EXISTING.
7. FIELD VERIFY ALL DOOR SIZES IN EXISTING OPENINGS PRIOR TO FABRICATION.
8. REINSTALL HOLD OPENS AND ALARM DEVICES ON ANY REPLACED EXISTING DOORS AS REQUIRED. REPLACE ANY OF THESE COMPONENTS AS REQUIRED IF CONDITION WARRANTS.
9. DOOR HARDWARE FINISH TO MATCH EXISTING. COORDINATE ANY DISCREPANCIES OR INCONSISTENCIES WITH THE OWNER.

A14	DOOR AND HOLLOW METAL FRAME TYPES
1/4" = 1'-0"	AE601

A7	WINDOW TYPES
1/4" = 1'-0"	AE601

REV	DESCRIPTION	DATE
0	PERMIT SET	7-1-16

PERMIT SET
7-1-16

CURRENT ISSUE STATUS:

PROJECT NORTH:

LICENSED ARCHITECT KRISTEN L. DANUTH No. 2793 STATE OF MAINE
July 16

SMRT Architects and Engineers
144 Fore Street
Portland, Maine 04104
1.877.700.7678
www.smrtinc.com
ARCHITECTURE | ENGINEERING | PLANNING | INTERIORS | ENERGY

MILLER DRUG FITUP
MERCY FORE RIVER MOB

195 Fore River Parkway, Portland, ME 04102

SCHEDULES & DETAILS

SHEET TITLE:

0 1/4" 1/2" 1" 2" 3"

SCALE: AS NOTED

PROJECT MANAGER:	KD	PROJECT NO:	16087
A/E OF RECORD:	KDD		
JOB CAPTAIN:	SHK		
DRAWN BY:	SHK		
SMRT FILE:	AE601-16087	SHEET No.	AE601

© COPYRIGHT 2015 SMRT INC.

Reviewed for Code Compliance
Approved as Noted
Date: 09/06/16

22x34