



MILLER DRUG FITUP - MERCY FORE RIVER MOB

PORTLAND, MAINE

KEY PLAN



PROJECT LOCATION



DRAWING LIST

<u>GENERAL</u>	
G1001	COVER SHEET
<u>ARCHITECTURAL</u>	
A-001	LIFE SAFETY AND WALL TYPES
AE101	FLOOR PLANS
AE121	REFLECTED CEILING PLAN
AE201	ELEVATIONS & SECTIONS
AE601	SCHEDULES & DETAILS
<u>STRUCTURAL</u>	
SG001	STRUCTURAL GENERAL NOTES
SF101	CANOPY FRAMING PLAN
<u>MECHANICAL</u>	
M-001	HVAC LEGEND & ABBREVIATIONS
M-002	HVAC SPECIFICATIONS
MH101	FIRST FLOOR HVAC DUCTWORK & PIPING PLAN
<u>PLUMBING</u>	
P-001	PLUMBING LEGEND & ABBREVIATIONS
P-002	PLUMBING SPECIFICATIONS
PL101	FIRST FLOOR PLUMBING PLANS
<u>ELECTRICAL</u>	
E-001	LEGEND AND GENERAL NOTES
E-002	SPECIFICATIONS
E-003	SPECIFICATIONS
E-004	SPECIFICATIONS
E-101	FIRST FLOOR ELECTRICAL PLANS

PROJECT GENERAL NOTES:

- FIELD VERIFY ALL DIMENSIONS AND LAYOUT PRIOR TO PROCEEDING WITH WORK. NOTIFY ARCHITECT IN WRITING OF ANY DISCREPANCIES OR INCONSISTENCIES. FAILURE TO REPORT ANY DISCREPANCIES WITHIN THESE CONSTRUCTION DOCUMENTS TO THE ARCHITECT WILL NOT BE GROUNDS FOR ADDITIONAL COST OR CHANGE ORDERS.
- CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING ALL MATERIALS (UNLESS NOTED OTHERWISE), AND WORKMANSHIP IN ACCORDANCE WITH FEDERAL, STATE, CITY AND LOCAL BUILDING CODES AND THEIR REQUIREMENTS.
- CONTRACTOR AND ALL TRADES SHALL NOTE REQUIREMENTS OF "GENERAL NOTES" ON ALL SHEETS.
- EACH TRADE TO PROVIDE SMOKE OR FIRE SEALANT AT PENETRATIONS AS REQUIRED FOR WALL TYPE. ALL SEALANT, FIRE STOPPING, AND SMOKE STOPPING ASSEMBLIES SHALL BE U.L. RATED.
- DIMENSIONS ARE CENTERLINE OF STUD PARTITIONS, UNLESS INDICATED OTHERWISE.
- REFER TO ALL CONSTRUCTION DOCUMENTS FOR REQUIREMENTS WHICH MAY AFFECT THE WORK IN ANOTHER DISCIPLINE AND COORDINATE WORK.
- REFER TO DETAILS FOR ADDITIONAL DIMENSIONAL INFORMATION.
- DOOR JAMBS SHALL BE LOCATED 6" FROM CORNER IN STUD PARTITIONS, UNLESS INDICATED OTHERWISE.
- PROVIDE BLOCKING IN WALLS AS NECESSARY WHERE CASEWORK, SHELVES, HANDRAILS, AND MISC. EQUIPMENT ARE LOCATED.
- DO NOT SCALE DRAWINGS.
- "PROVIDE" MEANS "FURNISH AND INSTALL".
- ELEVATIONS INDICATED ON THE GENERAL, ARCHITECTURAL, MECHANICAL, ELECTRICAL, FIRE PROTECTION AND PLUMBING DRAWINGS ARE BASED ON AN ASSIGNED REFERENCE ELEVATION OF THE CONCRETE SLAB = 0'-0".

SYMBOL LEGEND

	BUILDING SECTION		EXTERIOR ELEVATION		LEVEL LINE		ROOM NAME
	WALL SECTION		INTERIOR ELEVATION		CIRCLE NOTE		ROOM NUMBER
	DETAIL				WINDOW TAG		COLUMN BUBBLE AND CENTER LINE
					PARTITION TAG		BACKER ROD AND SEALANT
					DOOR TAG		

ABBREVIATIONS

AC, A/C	AIR CONDITIONING	FB	FLAT BAR	MB	MARKER BOARD	SACT	SUSPENDED ACOUSTIC
ACCU	AIR CONDITIONING CONDENSER UNIT	FBO	FURNISHED BY OTHERS	MDO	MEDIUM DENSITY OVERLAY	SC	TILE CEILING
ACPLAS	ACOUSTICAL PLASTER	FCO	FLOOR CLEAN-OUT	MO	MASONRY OPENING	SF	SOLID CORE
ACT	ACOUSTIC CEILING TILE	FCU	FAN COIL UNIT	MR	MOISTURE-RESISTANT	SK	SQUARE FOOT; SUPPLY FAN
AFF	ABOVE FINISHED FLOOR	FD	FLOOR DRAIN	MUA	MAKE-UP AIR	SN	SANITARY NAPKIN (DISPENSER)
AP	ACCESS PANEL	FE	FIRE EXTINGUISHER			SP	SPECIAL
		FF	FINISHED FLOOR; FAR FACE	N	NOSING	SS	STAINLESS STEEL
BCE	BOTTOM CHORD EXTENSION	FO	FRAMED OPENING	NIC	NOT IN CONTRACT	STL	STEEL
BD	BOARD	FRP	FIBERGLASS REINFORCED PLASTIC	NS	NEAR SIDE		
BEJ	BUILDING EXPANSION JOINT	FS	FLOOR SINK	NTS	NOT TO SCALE	T	TREAD
BLP	BORROWED LIGHT PANEL			OC	ON CENTER	TB	TACKBOARD
BO	BOTTOM OF	GB	GRAB BAR	OF	OUTSIDE FACE	T&B	TOP AND BOTTOM
BOF	BOTTOM OF FOOTING	GC	GENERAL CONTRACTOR	OH	OPPOSITE HAND; OVERHEAD	TBM	TEMPORARY BENCHMARK
BOS	BOTTOM OF STEEL	GDT	GYPSPUM DROP-IN TILE			TCE	TOP CHORD EXTENSION
BS	BOTH SIDES	GRD	BUILDING GRID LINE	PA	PUBLIC ADDRESS	TJ	TIE JOIST
BSE	BRICK SHELF ELEVATION	GV	GRAVITY VENT	PAF	POWDER-ACTUATED FASTENER	TO	TOP OF
		GWB	GYPSPUM WALL BOARD	PDU	POOL DEHUMIDIFICATION UNIT	TOC	TOP OF CONCRETE
C	CHANNEL			PEFS	PRECOMPRESSED EXPANDABLE FOAM SEALER	TOF	TOP OF FOOTING
CB	CATCH BASIN; CHALKBOARD	H	HORIZONTAL	PL	PLATE	TOHC	TOP OF HOLLOW CORE
CEM BD	CEMENTITIOUS BACKER BOARD	HC	HANDICAPPED; HOLLOW CORE	PLAM	PLASTIC LAMINATE	TOM	TOP OF MASONRY
CFM	CUBIC FEET PER MINUTE	HM	HOLLOW METAL	PLF	POUNDS PER LINEAR FOOT	TOP	TOP OF PIER
CIP	CAST IN PLACE	HP	HIGH POINT	PP	POWER PANEL	TOS	TOP OF STEEL; TOP OF SLAB
CJ	CONTROL JOINT; CONSTRUCTION JOINT	HRU	HEAT RECOVERY UNIT	PHC	PRECAST HOLLOW CORE	TOW	TOP OF WALL
CMU	CONCRETE MASONRY UNIT	H&V	HEATING AND VENTILATING	PSF	POUNDS PER SQUARE FOOT	TP	TOILET PAPER (DISPENSER)
CT	CERAMIC TILE	HVAC	HEATING, VENTILATING AND AIR CONDITIONING			UH	UNIT HEATER
CUH	CABINET UNIT HEATER	IF	INSIDE FACE	PSI	POUNDS PER SQUARE INCH	UNO	UNLESS NOTED OTHERWISE
COL	COLUMN GRID LINE	IJ	ISOLATION JOINT	PT	PRESSURE-TREATED	V	VENT PIPE; VERTICAL
CONT	CONTINUOUS	IMP	IMPACT RESISTANT	PVC	POLYVINYL CHLORIDE	VB	VAPOR BARRIER
		INSUL	INSULATION			VCT	VINYL COMPOSITION TILE
DF	DRINKING FOUNTAIN	INV	INVERT	R	RISER; RADIUS	VP	VISION PANEL
DR	DISPLAY RAIL	JS	JOIST SUBSTITUTE	RB	RESILIENT BASE	VTR	VENT THROUGH THE ROOF
DW	DISHWASHER			RD	ROOF DRAIN		

0	PERMIT SET	7-1-16
REV	DESCRIPTION	DATE

PERMIT SET
7-1-16
CURRENT ISSUE STATUS:



PROJECT NORTH:
SMRT Architects and Engineers
144 Fore Street
Portland, Maine 04104
1.877.700.7678
www.smrtinc.com

ARCHITECTURE | ENGINEERING | PLANNING | INTERIORS | ENERGY **SMRT**

**MILLER DRUG FITUP
MERCY FORE RIVER MOB**

195 Fore River Parkway, Portland, ME 04102

COVER SHEET

SHEET TITLE:

SCALE: AS NOTED

PROJECT MANAGER: KD PROJECT NO: 16087

A/E OF RECORD: KD
JOB CAPTAIN: SHK
DRAWN BY: SHK
SMRT FILE: G001-16087 SHEET No. **G1001**

© COPYRIGHT 2016 SMRT INC.