

## ROOM FINISH SCHEDULE

ROOM TAG	ROOM NAME	FLOOR	BASE	WALLS				CEILING		ROOM TAG	REMARKS	
				NORTH	SOUTH	EAST	WEST	MATERIAL	HEIGHT			
1120	WAITING	SEE AF101	RB	-	PTD	PTD	PTD	PTD	(E) ACT	EXIST	1120	
1121	RECEP/BUSINESS OFFICE	SEE AF101	RB	PTD	PTD	PTD	-	-	(E) ACT	EXIST	1121	
1125	CENTRAL REG.	SEE AF101	RB	PTD	-	-	PTD	PTD	(E) ACT	EXIST	1125	
1145	WAITING	SEE AF101	RB	PTD	PTD	PTD	PTD	PTD	ACT	SEE AE105	1145	
1146	DRAW	SEE AF101	RB	PTD	PTD	PTD	PTD	PTD	ACT	SEE AE105	1146	
1147	TOILET	SEE AF101	RB	PTD	PTD	PTD	PTD	PTD	ACT	SEE AE105	1147	
1148	DRAW	SEE AF101	RB	PTD	PTD	PTD	PTD	PTD	ACT	SEE AE105	1148	
1149	REG.	SEE AF101	RB	PTD	PTD	PTD	PTD	PTD	ACT	SEE AE105	1149	
1150	WORK AREA	SEE AF101	RB	PTD	PTD	PTD	PTD	PTD	ACT	SEE AE105	1150	
1151	CORRIDOR	SEE AF101	RB	PTD	-	-	-	-	(E) ACT	EXIST	1151	
1152	CORRIDOR	SEE AF101	RB	-	-	-	PTD	PTD	(E) ACT	EXIST	1152	
1155	CORRIDOR	SEE AF101	RB	-	PTD	-	-	-	(E) ACT/GWB	EXIST	1155	

LEGEND: PTD: PAINTED      GWB: GYPSUM WALL BOARD      ACT: ACOUSTIC CEILING TILE

### FINISH NOTES:

1. REFER TO RCP FOR SOFFIT HEIGHTS. ALL SOFFITS TO BE PAINTED.
2. ALL NEW FLOORING MATERIAL TO RUN BENEATH NEW CASEWORK UNLESS NOTED OTHERWISE.
3. ALL GYP. CEILINGS TO BE PAINTED.

144 Fore Street/P.O. Box 618  
 Portland, Maine 04104  
 tel. (207) 772-3846  
 fax. (207) 772-1070  
 www.smrtinc.com

ARCHITECTURE  
 ENGINEERING  
 PLANNING  
 INTERIOR DESIGN  
 COMMISSIONING



**MERCY HOSPITAL  
 FORE RIVER MOB LAB**  
 PORTLAND, MAINE

**ISSUED FOR PRICING  
 6-24-09**

REV	DESCRIPTION	DATE

SCALE: NTS  
 PROJECT MANAGER: GDP  
 JC/DRAWN BY: CAH  
 A/E OF RECORD: GDP  
 CAD FILE: AE601-09067-00  
 PROJECT NO: 09067-00  
 DATE:                      

SHEET TITLE:  
**FINISH SCHEDULE**

SHEET No.  
**AE601**