




A SHRUB INSTALLATION DETAIL
 N.T.S.



D TREE INSTALLATION DETAIL: >10' HT.
 N.T.S.



B MULTI-TRUNKED TREE INSTALLATION DETAIL
 N.T.S.



C TREE INSTALLATION DETAIL: <10' HT.
 N.T.S.

Product	Dero Downtown Rack As manufactured by Dero Bike Racks
Capacity	2 Bikes
Materials	2" x 2" x 3/16" tube
Finishes	As after fabrication hot dipped galvanized finish is standard. 250TGC powder coat color, a thermoplastic coating and a stainless steel option are also available. Our powder coat finish assures a high level of adhesion and durability by following these steps: 1. Sandblast 2. Iron phosphate pretreatment 3. Epoxy primer electrostatically applied 4. Final thick TGIC polyester powder coat Stainless Steel: 304 grade stainless steel material finished in either a high polished shine or a satin finish. A rubbery PVC Dip is also available.
Installation Methods	In ground mount is embedded into concrete base. Specify in ground mount for this option. Foot Mount has two 2.5" x 6" x .25" feet with two anchors per foot. Specify foot mount for this option. Rail Mounted Downtown Racks are bolted to two parallel rails which can be left freestanding or anchored to the ground. Rails are heavy duty 5" x 1.4" x .316" thick galvanized mounting rails. Specify rail mount for this option.
Space Use and Setbacks	Wall Setbacks: For racks set parallel to a wall: Minimum: 24" Recommended: 36" For racks set perpendicular to a wall: Minimum: 28" Recommended: 42" Distance Between Racks: Minimum: 24" Recommended: 36" Street Setbacks: Minimum: 24" Recommended: 36"

DATE: AUGUST 2009
 REVISED:
 CITY OF PORTLAND, MAINE
 TECHNICAL STANDARDS MANUAL
 TRANSPORTATION SYSTEMS
 AND STREET DESIGN
 SECTION 1
 BICYCLE RACK SPECIFICATION - DOWNTOWN RACK
 FIGURE:
I-34a
 69


MFR: DERO BIKE RACKS
 IN-GROUND MOUNT.
 POWDER COAT FINISH
 COLOR: BLACK
 www.dero.com
 1-800-298-4915

H BICYCLE RACK SPECIFICATION - DOWNTOWN RACK
 N.T.S.

V:\2108\active\210801661\civil\road\perm\fig\1006_congress_det.dwg 12/13/2018 2:11 PM

18.12.14
 DBS
 Appr.
 YJAW/DD
 1 - LEVEL B SITE PLAN APPLICATION SUBMISSION TO CITY
 Revision

File Name: 1006_congress_det CDD SRB DBS 18.11.27
 DWN. CHKD. DSGN. DATE



Client/Project
 PK Realty Management Investments
 380 Riverside Street, Portland, Maine
 1006 Congress Street
 Mixed-Use Redevelopment
 PORTLAND, MAINE

Title
DETAILS

Project No. 210801661 Scale N.T.S.

Sheet
C-6.2