

DISPLAY THIS CARD ON PRINCIPAL FRONTAGE OF WORK



CITY OF PORTLAND BUILDING PERMIT



This is to certify that

773 CONGRESS LLC

Located at

56 DOUGLASS ST

PERMIT ID: 2017-01102

ISSUE DATE: 04/19/2018

CBL: 078 A028001

has permission to **Legalization of 1 nonconforming dwelling unit for a total of three in the building** provided that the person or persons, firm or corporation accepting this permit shall comply with all of the provisions of the Statutes of Maine and of the Ordinances of the City of Portland regulating the construction, maintenance and use of the buildings and structures, and of the application on file in the department.

| | |
|---|---|
| Notification of inspection and written permission procured before this building or part thereof is lathed or otherwise closed-in. 48 hour notice is required. | A final inspection must be completed before this building or part thereof is occupied. If a certificate of occupancy is required, it must be procured prior to occupancy. |
|---|---|

/s/ Jason Grant

Fire Official

/s/ Brian Stephens

Building Official

**THIS CARD MUST BE POSTED ON THE STREET SIDE OF THE PROPERTY
THERE IS A PENALTY FOR REMOVING THIS CARD**

Approved Property Use - Zoning

three dwelling units

Building Inspections

Use Group: R-2 **Type:** 5B
Residential Apartment Building
Non-Sprinkled
Second Floor
MUBEC/IBC-2009

Fire Department

BUILDING PERMIT INSPECTION PROCEDURES
Please call 874-8703
or email: buildinginspections@portlandmaine.gov

**Check the Status of Permit or Schedule an Inspection at
<http://www.portlandmaine.gov/planning/permitstatus.asp>**

With the issuance of this permit, the owner, builder or their designee is required to provide adequate notice to the City of Portland Inspections Division for the inspections listed below. Appointments must be requested 48 to 72 hours in advance. The inspection date will need to be confirmed by this office.

- **Please read the conditions of approval that are attached to this permit.**
- **Permits expire in 6 months if the project is not started or ceases for 6 months.**
- **If the inspection requirements below are not followed, then additional fees may be incurred due to the issuance of a "Stop Work Order" and subsequent release to continue.**
- **Per Section 107.3.1 of the Maine Uniform Building and Energy Code (MUBEC), one set of printed approved stamped construction documents will be kept at the site of work and open to inspection by building officials.**

REQUIRED INSPECTIONS:

Final Inspection

Final - Fire

The project cannot move to the next phase prior to the required inspection and approval to continue.

If the permit requires a certificate of occupancy, it must be paid and issued to the owner or designee before the space may be occupied.

| | | | | |
|---|--|--|--|----------------------------------|
| City of Portland, Maine - Building or Use Permit | | Permit No: 2017-01102 | Date Applied For: 07/10/2017 | CBL: 078 A028001 |
| 389 Congress Street, 04101 Tel: (207) 874-8703, Fax: (207) 874-8716 | | | | |
| Proposed Use: 3 Family | | Proposed Project Description: Legalization of 1 nonconforming dwelling unit for a total of three in the building | | |
| Dept: Zoning | | Status: Approved w/Conditions | Reviewer: Christina Stacey | Approval Date: 04/05/2018 |
| Note: | | Ok to Issue: <input checked="" type="checkbox"/> | | |
| Conditions: | | | | |
| <ol style="list-style-type: none"> 1) Upon issuance of the Certificate of Occupancy, this property shall remain three dwelling units. Any change of use shall require a separate permit application for review and approval. 2) This permit is being approved on the condition that the applicant completes all required work to bring the property into compliance with the applicable housing and life safety codes. A Certificate of Occupancy for the legalized unit shall not be issued until such work is completed, as verified by a final inspection. If a Certificate of Occupancy is not issued, the approval of the legalized unit is void and the applicant shall be required to remove the unit. | | | | |
| Dept: Building Inspecti | | Status: Approved w/Conditions | Reviewer: Brian Stephens | Approval Date: 04/18/2018 |
| Note: | | Ok to Issue: <input checked="" type="checkbox"/> | | |
| Conditions: | | | | |
| <ol style="list-style-type: none"> 1) Separate permits are required for any electrical, plumbing, sprinkler, fire alarm, HVAC systems, heating appliances, including pellet/wood stoves, commercial hood exhaust systems, fire suppression and fuel tanks. Separate plans may need to be submitted for approval as a part of this process. 2) This permit recognizes a pre-existing land use and does not require or certify compliance with the City's current building code. The inspection performed will be done pursuant to the City's Minimum Standards for Housing, The Housing Code. All violations shall be corrected prior to the final inspection and the issuance of the Certificate of Occupancy. 3) All existing fire separation partitions, barriers and horizontal assemblies at adjacent occupancies or dwelling units shall be maintain for rating and continuity. Additional materials may need to be added for compliance. 4) Egress size windows are required (1) in each sleeping room per the Permitting and Inspections and the State Fire Marshal policies for existing buildings. 5) The issuance of this permit shall not be construed to be a permit for, or approval of, any violations of any of the provisions of the building code or of any other ordinance of this jurisdiction. 6) This permit is approved based upon information provided by the applicant or design professional. Any deviation from the final approved plans requires separate review and approval prior to work. | | | | |
| Dept: Fire | | Status: Approved w/Conditions | Reviewer: Jason Grant | Approval Date: 04/09/2018 |
| Note: | | Ok to Issue: <input checked="" type="checkbox"/> | | |
| Conditions: | | | | |
| <ol style="list-style-type: none"> 1) Hazardous area such as boilers and laundry room outside of the dwelling units shall be protected by a 1-hour fire resistance rated enclosure or sprinkler protection. 2) Per NFPA 101 section 7.1.3.2.1 exits and stairways in building 3 or fewer stories in height shall be constructed of a 1-hour fire resistance rated walls and ceilings and shall have 1-hour self-closing and latching fire rated doors at all openings. 3) Every sleeping and living area in a residential occupancy shall have at least 1 primary means of escape and 1 secondary means of escape. The secondary means of escape may be an outside egress window operable from the inside without the use of tools, keys or special effort. In buildings built before 1976, egress windows shall provide a net clear opening 3.3 sq. ft. The width shall not be less than 20 inches and height shall not be less than 24 inches. In addition, if all window parts were removed the entire opening must be 5.0 sq. ft. in size. The bottom of the window opening shall not be more than 44 inches above the floor unless a permanent step is installed. The opening shall also meet the other requirement of NFPA 101 section 24.2.2.3.3. | | | | |

PERMIT ID: 2017-01102

Located at: 56 DOUGLASS ST

CBL: 078 A028001

- 4) City of Portland Code Chapter 10 section 10-3 (L) all residential occupancies, and all new multiple occupancies containing attached parking structures or fuel burning appliances shall be protected in accordance with NFPA 720, Standard for the Installation of Carbon Monoxide (CO) Detection and Warning Equipment, 2009 edition. Detectors shall be provided in the following areas.
 1. Outside each separate sleeping area, in the immediate vicinity of the sleeping areas
- 5) City of Portland Code Chapter 10 section 10-3 (i) all new smoke alarm must use photoelectric technology. In existing apartment building smoke detectors must be powered by the buildings electrical service and must have a secondary power source (battery). Smoke Alarms shall be installed per NFPA 101 2009 section 9.6.2.10. Detectors are required to be installed in the following locations
 1. Inside all sleeping rooms.
 2. Outside each separate sleeping area, in the immediate vicinity of the sleeping areas
 3. On each level of the dwelling unit, including basements but excluding attics and crawl spaces.
- 6) All construction shall comply with City Code, Chapter 10.
All construction shall comply with 2009 NFPA 101 Life Safety Code, Chapter # 43 and other applicable chapters
All construction shall comply with 2009 NFPA 1, Fire Code.
This review and approval by the AHJ shall not relieve the applicant of the responsibility of compliance with this Code. NFPA 1 (section 1.14.4).
All means of egress to remain accessible at all times.
If applicable, all outstanding code violations shall be corrected prior to final inspection.