

FREE PARCEL SHIPPING WITH MYLOWE'S. GET STARTED >



Open until 10PM!
Scarborough Lowe's ▾

Prices, promotions, styles, and availability may vary. Our local stores do not honor online pricing. Prices and availability of products and services are subject to change without notice. Errors will be corrected where discovered, and Lowe's reserves the right to revoke any stated offer and to correct any errors, inaccuracies or omissions including after an order has been submitted.

JELD-WEN V-2500 Vinyl Double Pane Double Strength New Construction Double Hung Window (Rough Opening: 32-in x 60-in; Actual: 31.5-in x 59.5-in)

Item # 407539 Model #
LOWOLVYDHDL3260

☆☆☆☆☆ No reviews

\$260.36

− 1 +

ADD TO CART

♡ SAVE ↗ SHARE



Ships to Store FREE

✓ Ready for pickup on
08/09/2017 at Scarborough
Lowe's



Delivery

✓ Ready for delivery on
08/09/2017 at Scarborough
Lowe's



Get 5% OFF* Every Day

Subject to credit approval. Exclusions apply. Cannot be combined with Special Financing.

[Get Details >](#)

[CHAT WITH LOWE'S](#)

Product Information



Description



- JELD-WEN V2500 vinyl windows are made to be durable, energy efficient and attractive
- Built from high-quality extruded vinyl that resists fading and won't chip or peel
- This product is backed by our lifetime warranty that is transferable for 10 years
- Our high-performance, Low-E 366 insulating glass lowers energy costs, helps homes stay cooler in the summer and warmer in the winter
- Both sash tilt in for convenient cleaning
- 1-1/4-in pre-punched nailing fin integral to the frame, it surrounds the full perimeter of the frame and helps make installations weather-tight
- Grilles between the glass will add character to your home and require no upkeep - will not interfere with window cleaning
- If you're not seeing what you want, optional colors and custom sizes are available - check with your local Lowe's store

Do you need some help?

CHAT NOW



Specifications

Actual Height (Inches)	59.5	Lock Type	Cam
Actual Width (Inches)	31.5	Nail Fin	Integrated
Jamb Depth (Inches)	3.563	J Channel	N/A
Series	V-2500	Mulling	Field applied
Interior Color/Finish	White	Wood Jamb Extension	None
Exterior Color/Finish	White	Number of Locks	2
Hardware Color/Finish	White	Ventilation Latches	N/A
Paintable	×	Tilt Mechanism	Raised
Color/Finish Family	White	High Altitude Rated	×

Frame Material	Vinyl	Hurricane Approved	×
Grid Type	Between the glass	Miami Dade Approved	×
Grid Width	5/8-in	Sound Transmission Control (STC) Rated	✓
Grid Profile	Flat	Florida Product Approved	×
Grid Pattern	3W2H	Design Pressure (DP) Rating	20
Argon Gas Insulated	✓	Texas Department of Insurance Approved	×
Glass Strength	Double strength	U Value	0.32
Obscure Glass	×	Meets CA Forced Entry Requirements	×
Frame Profile	Flat	Solar Heat Gain Coefficient (SHGC)	0.19
Screen Included	Full	Grid Included	✓
Screen Type	Fiberglass mesh	ENERGY STAR Certified Northern Zone	×
Screen Frame Type	Extruded	ENERGY STAR Certified North/Central Zone	✓
Balance System	Block and tackle	ENERGY STAR Certified South/Central Zone	✓
Tilting	✓	ENERGY STAR Certified Southern Zone	✓
Warranty	Limited lifetime	Rough Opening Width (Inches)	32.0
Lowe's Exclusive	×	Rough Opening Height (Inches)	60.0
Project Type	New construction	Glazing Type	Double pane
Meets Egress Requirement	×	Glass Insulation	Dual-pane

Projects, Tips & Services



Window Installation



Weather Strip Your Windows

Need Help?

Call 1-800-445-6937

Products & Sales

Call 1-877-GO-LOWES

© 2017 Lowe's. All rights reserved. Lowe's and the gable design are registered trademarks of LF, LLC.