Saint John Street Apartment | 16019 | March 8,

CONTRACT DOCUME

08 90 00

WINDOW SCHEDULE

Reviewed for Code Compliance
Inspections Division
Approved with Conditions
Date: 05/05/17

No.	Window Manufactuer	Model No.	Unit Type	Rough Opening	Window Size	Required Egress	Low "E2" with Argon Insul. Glass (5)	Insect Screen	Pre-finished Grills between Glass	Pntd. 1x wd extension Jambs on four sides	Pntd. Wood casing (see details)	Integral standard flat Casing	Quanity (Contractor to verify)	Comments
A	Paradigm Window or Equal	Craftec	Single Hung (Triple) w/ standard mull	7'-11 1/2" W x 3'-2 1/2" H +/- V.I.F.	7'-11" W x 3'-2" H +/- V.I.F.	No	Yes	Yes		Yes	Yes	No		see dwg A8.01 & A8.02 for detail
B	Paradigm Window or Equal	Craftec	Single Hung Window	3'-1 1/2" W x 3'-2 1/2" H +/- V.I.F.	3'-1" W x 3'-2" H +/- V.I.F.	No	Yes	Yes		Yes	Yes	No		see dwg A8.01 & A8.02 for detail
B1	**Kohltech Window or Equal**		**Tilt & Turn**	**3' - 1 1/4" W x 3'-0 3/4" H**	**3'-0" W x 2'-11 1/2" H**	**Yes**	**Yes**	**Yes**		**Yes**	**Yes**	**No**		**see dwg A8.01 & A8.02 for detail**
C	Paradigm Window or Equal	Craftec	Single Hung Window	1'-7 1/2" W x 3'-2 1/2" H +/- V.I.F.	1'-7" W x 3'-2" H +/- V.I.F.	No	Yes	Yes		Yes	Yes	No		see dwg A8.01 & A8.02 for detail
D	Paradigm Window or Equal	Craftec	Single Hung Window	3'-0 1/2" W x 4'-4 1/2" H +/- V.I.F.	3'-0" W x 4'-4" H +/- V.I.F.	No	Yes	Yes		Yes	Yes	No		see dwg A8.01 & A8.02 for detail
E	Paradigm Window or Equal	Craftec	Awning vinyl window	3'-0 1/2" W x 2'-1 1/2" H +/- V.I.F.	3'-0"W x 2'-1" H +/- V.I.F.	No	Yes	Yes		Yes	Yes	No		see dwg A8.01 & A8.02 for detail
F	Paradigm Window or Equal	Craftec	Awning vinyl window	3'-9 1/2" Wx4'-1 1/2" H +/- V.I.F.	3'-9 1/2" Wx4'-1 1/2" H +/- V.I.F.	No	Yes	Yes		Yes	Yes	No		

General Notes

1. Verify Rough Openings Prior to Framing

2. Insulate Between Window and Rough Opening as recommended by window manufacturer with non-expansive foam.

3. Provide Safety Glazing at all doors and sidelites and at windows as indicated on the drawings - refer specification for more information.

4. Provide Insulated Glazing throughout as per specification.

5. existing inteiror casing - see drawing A8.02 / A3 for detail

6. Provide Single Hung windows with Double Balance Hardware.

WS