
**CITY OF PORTLAND
HOUSING SAFETY OFFICE**

389 Congress Street
Portland, Maine 04101

Inspection Violations

Owner/Manager FORTY NINE LLC		Inspector David Petruccelli	Inspection Date 2/10/2017
Location 202 DARTMOUTH ST	CBL 081 A010001	Status Failed	Inspection Type Legalize Nonconforming units

Code	Int/Ext	Floor	Unit No.	Area	Compliance Date
-------------	----------------	--------------	-----------------	-------------	------------------------

1) 69.20

Violation: PORTLAND FIRE DEPARTMENT CHAPTER 10 SECTION 12 KNOX BOX REQUIRED; KNOX BOXES ARE REQUIRED FOR ALL BUILDINGS WITH FIRE ALARM OR SUPPRESSION SYSTEMS.

Notes:

2) 80.16

Violation: NFPA 101-7.9.3 EMERGENCY LIGHTS REQUIRE MAINTENANCE; 7.9.3 Periodic Testing of Emergency Equipment

7.9.3.1 Required emergency lighting systems shall be tested in accordance with one of the three options offered by 7.9.3.1.1, 7.9.3.1.2, or 7.9.3.1.3.

7.9.3.1.1 Testing of required emergency lighting systems shall be permitted to be conducted as follows:

(1) Functional testing shall be conducted monthly with a minimum of 3 weeks and a maximum of 5 weeks between tests, for not less than 30 seconds, except as otherwise permitted by 7.9.3.1.1(2).

(2) The test interval shall be permitted to be extended beyond 30 days with the approval of the authority having jurisdiction.

(3) Functional testing shall be conducted annually for a minimum 1-1/2 hours if the emergency lighting system is battery powered.

(4) The emergency lighting equipment shall be fully operational for the duration of the test required by 7.9.3.1.1(1) and (3).

(5) Written records of visual inspections and tests shall be kept by the owner for inspection by the authority having jurisdiction.

Notes: Not working on floor 1

3) 80.46

Violation: NFPA 101- 7.2.1.8.1 FIRE DOORS MUST BE SELF- OR AUTO-CLOSING; A door leaf normally required to be kept closed shall not be secured in the open position at any time and shall be self-closing or automatic-closing in accordance with 7.2.1.8.2, unless otherwise permitted by 7.2.1.8.3.

Notes: Self-closing hinges required on unit doors and mechanical/laundry spaces

4) 55.15

Violation: NFPA 101- 31.3.4.1.1 FIRE ALARM SYSTEM REQUIRED; Apartment buildings four or more stories in height or with more than 11 dwelling units, other than those meeting the requirements of 31.3.4.1.2, shall be provided with a fire alarm system in accordance with Section 9.6, except as modified by 31.3.4.2 through 31.3.4.6.

Notes: 12 units in building

CITY OF PORTLAND
HOUSING SAFETY OFFICE

389 Congress Street
Portland, Maine 04101

Inspection Violations

Owner/Manager FORTY NINE LLC		Inspector David Petruccelli	Inspection Date 2/10/2017
Location 202 DARTMOUTH ST	CBL 081 A010001	Status Failed	Inspection Type Legalize Nonconforming units

5) 55.25

Violation: NFPA 101- 31.3.4.5.1 SMOKE ALARMS REQUIRED; In buildings other than those equipped through out with an existing, complete automatic smoke detection system, smoke alarms shall be installed in accordance with 9.6.2.10, as modified by 31.3.4.5.2, outside every sleeping area in the immediate vicinity of the bedrooms and on all levels of the dwelling unit, including basements.

Notes: Photo-electric technology required

6) 91.15

Violation: NFPA 70- ARTICLE 110.12 B EXPOSED WIRING CONNECTIONS; Internal parts of electrical equipment, including busbars, wiring terminals, insulators, and other surfaces, shall not be damaged or contaminated by foreign materials such as paint, plaster, cleaners, abrasives, or corrosive residues. There shall be no damaged parts that may adversely affect safe operation or mechanical strength of the equipment such as parts that are broken; bent; cut; or deteriorated by corrosion, chemical reaction, or overheating.

Notes: laundry room above dropped ceiling

Comments: