

DEMO GENERAL NOTES:

 Contractor is responsible for temporary shoring with demolition of load bearing walls

2. Any material suspected of containing hazardous material should not be disturbed until proper inspections and remediation can be preformed.

3. Contractor to coordinate with Owner for all items to be saved/salvaged or reused in new scope of work.

DEMO SYMBOL LEGEND:

WALL TO BE DEMOLISHED

EXISTING WALL TO REMAIN

ROOM/AREA TO BE GUTTED, SEE ADDITIONAL NOTES

DOOR TO BE DEMOLISHED

FIXTURE/OBJECT TO BE DEMOLISHED

