D1 DEMOLITION 1ST FLOOR PLAN
SCALE: 1/4" = 1'-0"

0 2' 4' 8'

DEMO GENERAL NOTES:

1. Contractor is responsible for temporary shoring with demolition of load bearing walls
2. Any material suspected of containing hazardous material should not be disturbed until proper inspections and remediation can be preformed.
3. Contractor to coordinate with Owner for all items to be saved/salvaged or reused in new scope of work.

DEMO SYMBOL LEGEND:

- WALL TO BE DEMOLISHED
- EXISTING WALL TO REMAIN
- ROOM/AREA TO BE GUTTED, SEE ADDITIONAL NOTES
- DOOR TO BE DEMOLISHED
- FIXTURE/OBJECT TO BE DEMOLISHED

D2 DEMOLITION 2ND FLOOR PLAN
SCALE: 1/4" = 1'-0"

0 2' 4' 8'

A1 PROPOSED 1ST FLOOR OF GARAGE
SCALE: 1/4" = 1'-0"

0 2' 4' 8'

PROPOSED PLAN GENERAL NOTES:

1. All dimensions are from face of stud to face of stud (or from structural core to structural core) unless noted otherwise. Do not scale drawings, contact Architect for clarifications as needed.

PROPOSED PLAN SYMBOL LEGEND:

- NEW INSULATED EXTERIOR WALL SEE SECTIONS FOR MORE INFORMATION
- NEW INTERIOR WALL SEE WALL TYPES FOR MORE INFORMATION
- EXISTING WALL TO REMAIN
- NOT IN SCOPE
- WINDOW ETR= EXISTING TO REMAIN
- DOOR ETR = EXISTING TO REMAIN
- TAG-1 APPLIANCE/EQUIPMENT See Schedule A-0.2
- 1 / A-3.1 SECTION/DETAIL MARKER - Refer to Drawing; SHEET NUMBER; SHEET NUMBER
- 1 / A-2.1 ELEVATION MARKER - Refer to Drawing; SHEET NUMBER; SHEET NUMBER

A2 PROPOSED 2ND FLOOR OF GARAGE
SCALE: 1/4" = 1'-0"

0 2' 4' 8'

CALEB JOHNSON ARCHITECTS + BUILDERS
265 MAIN STREET, SUITE 201 BIDDEFORD, ME 04005 C.JAB.ME
T: 207.283.8777 F: 207.283.8778

STUDIO MANAGER:
PROJECT ARCHITECT:

CHANGES THIS ISSUE:

ID	DESCRIPTION

SUBMISSIONS:

ISSUE	DATE	DESCRIPTION
01	12/8/15	PERMIT SET

CONSULTANTS:
Aaron Jones, PE
Structural Integrity
77 Ocean Avenue, Portland, ME 04101
Matt Legere, E.I.T.

DRAFTSPERSON: Patrick Boothe, AIA
DATE OF ISSUE: 12/8/15
PROJECT STATUS: Schematic Design

Swenson Garage Renovation

Dana & Jane Swenson
114 Noyes Street Portland ME 04103

PERMIT SET

PROPOSED 1ST FLOOR GARAGE

A-1.0

Inspections Division
Date: 12/28/15
/Users/Patrick/Desktop/Server Backup/Swenson Phase 2/Swenson Phase 2.pln