Inspections Division
Date: 03/17/14

Lenehan/Gelman

General Notes:

Energy Standards:
- 2x6 framing with Dense Pack Cellulose (R-21)
- 1" foam on exterior (R-5)
- Total Wall R Value = R26
- Loose fill Cellulose at 2nd Floor Attic - R50
- Air Seal MEP penetrations
- Vent Channels as needed

Window Schedule:

All windows Andersen 400 Series White Vinyl, High Performance Low-E4 Glass

W1-	AW251 (V)	
W2-	A21 (V)	
W3-	TWT210111	
W4-	TWT21031 (F)	
W5-	TW2456E (AA)	
W6-	TW2452 (AA)	
W7-	TW21036 (AA)	
W8-	TW210410	(AA)
W9-	TW21042 (AA)	
W10-	TW21036 (AA)	
W11-	TW2642 (AA)	

Door Schedule:

D1-	30/68 Full View LH Fiberglass Entrance Door 6 9/16 jamb Flat Vinyl Casing Dbl Bore
D2-	30/68 Full View RH Fiberglass Entrance Door 6 9/16 jamb Flat Vinyl Casing Dbl Bore
D3-	22/68 4 Panel Pine RH Solid Jamb 4 9/16 Single Bore
D4-	20/68 4 Panel Pine RH Solid Jamb 4 9/16 Single Bore
D5-	26/68 4 Panel Pine LH Solid Jamb 4 9/16 Single Bore
D6-	50/68 4 Panel Pine "His/Her" Prehung Solid Jamb 4 9/16 No Bore (2- 26/68 slabs)
D7-	30/66 Flat Metal 20 min Fire Door Prehung 4 9/16 jamb

Basement Stair Information:

Rise: 7.375" FAILING TO CODE
Run: 10"

1 FIRST FLOOR PLAN
SCALE: 1/4" = 1'-0"

Linda Braley
44 Edwards St.
Portland, Maine 04102
lsbraley@yahoo.com
207.321.5060

DRAWING TITLE: FIRST FLOOR PLAN

PROJECT NAME: LENEHAN RESIDENCE
PORTLAND MAINE

THIS DRAWING IS THE PROPERTY OF LINDA BRALEY AND IS NOT TO BE COPIED OR REPRODUCED IN PART OR WHOLE. 2013 © LINDA BRALEY

DATE OF ISSUE
SEPT 26, 2013
DESCRIPTION
CONCEPTUAL
SCALE
1/4" = 1'-0"
PROJECT NUMBER
2013-0800

A-101