

CITY OF PORTLAND
 FIRE PREVENTION BUREAU
 380 Congress Street, Portland, Maine 04101
 fireprevention@portlandmaine.gov
 (207) 874-8400

NOTICE OF VIOLATION AND ORDER TO CORRECT

January 12, 2018

Viola Conti
 1 Naumburg Way
 Windham ME 04062

Location 160 NOYES ST	CBL 082 A027001	Inspection Date 11/20/2017
Inspector John Cenate	Inspection Type FP Routine Inspection	Status Failed

The City of Portland Fire Department inspected this property, and found the fire and life safety code violations listed below, which you are hereby ordered to correct. You must propose a date of completion to remedy each violation, a final date of completion, and a date of re-inspection.

You must send this form to the Fire Prevention Bureau no later than 1/30/2018.

Your failure to submit a plan of action by the date provided, or to correct any violation within the applicable time frame, may result in legal action against you, the imposition of civil penalties, and the pursuit of other legal remedies.

Violation	Proposed Date of Completion
NFPA 101-7.10.5.1 NORMAL ILLUMINATION FOR EXITS; Every sign required by 7.10.1.2, 7.10.1.5, or 7.10.8.1, other than where operations or processes require low lighting levels, shall be suitably illuminated by a reliable light source. Externally and internally illuminated signs shall be legible in both the normal and emergency lighting mode. front and rear stairs	___/___/___
NFPA 1 EXCESSIVE/DISORDERLY STORAGE; Reference NFPA 1 for excessive fuel-load. remove storage in the rear hall	___/___/___
NFPA 70- ARTICLE 110 B CERTIFY ELECTRICAL SYSTEM; Listed or labeled equipment shall be installed and used in accordance with any instructions included in the listing or labeling. Entire electrical system needs to be looked at. The fuse box need needs to be evaluated by a licensed electrician and a letter of compliance with the current electrical code shall be provided to Fire Prevention.	___/___/___
NFPA 101- 31.3.2.1.1 BOILER PROTECTION REQUIRED; The areas described in Table 31.3.2.1.1 shall be protected as indicated: Boiler and fuel-fired heater rooms serving more than a single dwelling unit (minimum separation/protection is 1 hour or sprinklers) Domestic sprinkler head is required over the fuel fired furnace and water heater.	___/___/___
NFPA 101- 8.3.4.2 60 MINUTE FIRE DOOR REQUIRED; Refer to NFPA 101- Table 8.3.4.2 that states fire door assemblies for vertical shafts (including stairways, exits, and refuse chutes) are rated and required for 1 hour. Any apartment door (front and rear) that enters into a stairwell or common area must be 60 minute rated and must have self-closing hardware to allow the door to self-close and latch. The basement doors are also included in this requirement.	___/___/___

Violation	Proposed Date of Completion
FINAL DATE OF COMPLETED VIOLATION(S)	___/___/___
FIRE PREVENTION BUREAU RE-INSPECTION OF COMPLETED VIOLATION(S)	___/___/___

The Bureau reserves the right to reject or modify any proposed plan of action, and may require evidence of sufficient financial and technical capacity to complete the proposed plan. Please contact the Bureau with any questions.

VIOLATOR CERTIFICATION

I agree to remedy the violations listed within the timeframes provided. If I require additional time to comply, I understand that I must contact the Fire Prevention Bureau prior to the deadline to request an extension, which is entirely within the Bureau's discretion to grant or deny.

I further understand that it is my responsibility to schedule a reinspection of my property once the violations have been remedied to do so. My failure to schedule a reinspection shall be deemed an admission that the violations have not been remedied.

If I fail to comply with this agreement, I understand that I am liable for penalties pursuant to the City of Portland Code of Ordinances §§ 1-15 and 10-25, and 30-A M.R.S. § 4452 and may be subject to further legal action.

Date Responsible Party

Date Responsible Party

SEEN AND AGREED

Date Fire Prevention Bureau