Inspection Division
Date: 06/28/17

PLANT SCHEDULE

Key	Botanical Name	Common Name	QTY	Size
1	Betula nigra	River Birch	3	10'-12" Clump
4	Ilex verticillata 'Winter Red'	Winter Red Winterberry	3	5 Gallon
5	Rhododendron 'Nova Zembla'	Nova Zembla Rhododendron	3	5 Gallon
6	Rhododendron ' Olga'	Olga Rhododendron	3	18" 3 Gallon
10	Viburnum plicatum 'Shasta'	Shasta Doublefile Viburnum	1	7 Gallon

BALL & BURLAP TREE OR SHRUB PLANTING DETAIL

Scale: not to scale

Prune off extraneous roots above the root flare.

Remove all soil above the root flare (two or more major roots).

Remove any clinging roots.

Planting hole to be approximately twice the width of the plant ball.

Taper and score the sides of the planting hole.

Hole to be no deeper than the height of the ball to the root flare.

Backfill hole in lifts, with soil removed from the hole, watering with each lift.

If native soils are heave clay, use new loam (unamended) as backfill and provide adequate drainage for water to leave hole. Plant high.

Apply mycorizal (Mycore) root inoculant in top third of backfill.

Slope backfill away from trunk, forming a small berm at the outside edge of the rootball to collect water.

Remove top 1/3 of wire basket and all wrapping above teh remaining basket.

Remove any twine, wire, all plastic materials around the ball or trunk.

Cut holes in remaining burlap.

Prune to remove
- broken and damaged branches
- weak crotch angles and water sprouts
- crossed and rubbing branches
- suckers and co-dominant suckers

Shape and this as necessary

Remove all tags, ribbons, and twine from the plant branches.

Stake tree only if in a hige wind condtion, tree is tall with a small root ball, or tree has an over 2.5" cal. dia. trunk.

Anchor guys in undisturbed soil only. Attach guys to trees above branches. Any non-rubber guys touching the tree shall be cusioned with rubber pads to prevent chafing. All guys to be installed at a 30-45 degree angle.

Any stakes or guys shall be installed loosely. The owner shall remove all stakes or guys after the first full growing season.

Apply a 3" layer of dark, composted bark mulch.

Berm the outside edge of mulch to act as a water dam.

Do not allow mulch to touch the bark of the tree trunk.

Owners to water with deep watering as instructed.

Deep water with to equal 5 gal. per 1" cal. dia. of trunk, twice weekly for one month, once weekly until frost unless directed otherwise.

NOTE:
Please note all information on this plan is conceptual. All locations and dimensions are illustrative only and shall be verified in the field. All construction and planting shall be on the owner's property only unless the owner has, in writing, permission from the owner of the other property. The owners shall locate property boundaries and site constraints (electrical service, leach beds, septic tanks, for example) with installation crews. Underground and unknown conditions are not included on this plan except as might be shown as a general illustration.

This is a Design/Build plan and may be intended to be phased. Some portions of this plan may not be included in a particular construction phase. Not all specifications for construction are on the plan. When in doubt, owners should refer to their contracts to review what is included in a specific construction phase.

If this plan is installed by anyone or any company other than Gnome Landscapes, Design & Masonry, the accuracy of all the components of the plan and the structural integrity of any portion of the construction based on the plan becomes solely the responsibility of the property owner.

0 4' 8' 12'
SCALE: 1/4" = 1'-0"

Date: 3/10/17
Designer: CGM
Revisions: 4/4/17

© 2017 Gnome LDM

GNOME
Landscapes, Design,
Masonry & Maintenence

305 US Route 1
PO Box 66803
Falmouth, Maine 04105
tel: 207-781-2955
fax: 207-781-5705
Web: GnomeLandscapes.com

Landscape Plan

DAY&DUGGAN RESIDENCE

30 WADSWORTH ST. PORTLAND, MAINE