



EXISTING
DOOR

DO NOT USE MAX NAILING SCHEDULE FOR ALL HANGERS

(3) 2x10 BEAM IS TO BE SOLID. BEAM TO BE NAILED EVERY 16" WITH (3) 20d GALV NAILS AND GRUED WITH CONSTRUCTION ADHESIVE JOINTS OF BEAM ARE TO BREAK OVER POSTS, AND OVER LAP 7' ON BEAMS

2x10 JOISTS (PT) 16" DC
DOUBLE ALL SIDE AND END JOISTS
SOLID 2x10 MIDLINER BLOCKING
LDS 2x10 AT ENDS OF EACH JOIST

(2) 1/2 GALVANIZED
CARPENT BOLTS
AT EACH STUD
THRU LEDGER

(3) 2x10 PT BUILD UP BEAM