KEY
SEE LIGHTING SCHEDULE FOR MORE INFORMATION

- RECESSED CEILING FIXTURE
- SURFACE MOUNT CEILING FIXTURE
- PENDANT FIXTURE
- WALL SCONCE
- POST LIGHT
- CABLE TRACK LIGHTING
- FLUORESCENT TUBE LIGHT
- 12V LINEAR LED W/ REMOTE TRANSFORMER, 2700K
- MONOPOINT LIGHT
- EXTERIOR FLOOD LIGHT
- DENOTES EXISTING FIXTURE
- EXTERIOR RECESSED FLOOR FIXTURE
- RECESSED CEILING FIXTURE (EXTERIOR) GAVL
- WALL SWITCH
- 3-WAY WALL SWITCH
- FAN SWITCH
- DUPLEX RECEPTACLE
- 220 VOLT RECEPTACLE
- GFI RECEPTACLE
- DUPLEX FLOOR RECEPTACLE
- DATA AND/OR TV
- FAN/LIGHT COMBO FIXTURE
- THERMOSTAT
- RECESSED CEILING SPEAKER

NOTES:

TOP OF ALL SWITCHES TO BE MOUNTED AT 48" AFF UNLESS OTHERWISE NOTED.

RECESSED LIGHTS TO BE ELITE 4" LOW VOLTAGE SERIES, WHITE.

ALL EXPOSED CONDUIT TO BE GALVANIZED RIGID CONDUIT, BOXES TO MATCH.

SMOKE DETECTORS/CO PER SECURITY SYSTEM SPECIFICATIONS.

ALL LIGHTING CIRCUITS TO BE ON DIMMERS.

CONVENTIONAL JAMB SWITCHES AT ALL CLOSETS

NO MORE THAN 4 SWITCHES GANGED IN ONE BOX. IF MORE THAN 4 SWITCHES ARE REQUIRED, STACK 2 BOXES ABOVE ONE ANOTHER WITH EQUAL NUMBER OF SWITCHES IN EACH BOX. USE DUMMY SWITCH IF NECESSARY.

MAINTAIN EXISTING OUTLETS UNLESS OTHERWISE NOTED.
OUTLETS TO CODE AS REQ'D.

REPLACE ALL EXISTING SWITCH PLATES TO MATCH NEW.

SPEAKERS TO BE WIRED W/ 16/4 CL2 IN-WALL SPEAKER WIRE, TYP.

1 BASEMENT ELECTRICAL PLAN
¼" = 1'-0"

FINE LINES CONSTR

Reviewed for Code Compliance
Inspections Division
Approved with Conditions
Date: 11/10/14

194 MAIN STREET · PO BOX 445 · FREEPORT, ME 04032
207-846-1002
FINELINESMAINE.COM

These drawings convey design intent only and should not be relied upon for building purposes unless stamped "for construction". See cover sheet for legal disclaimer and additional info.
These drawings shall not be reproduced without written permission from Fine Lines Construction, Inc.

© COPYRIGHT 2012 FINE LINES CONSTRUCTION, INC.

Renovations to the COOPER RESIDENCE

44 McKinley Court - Diamond Cove,
Great Diamond Island, ME 04109

Sheet Title:
BASEMENT ELECTRICAL PLAN

Issue Status:
PERMIT SET
OCTOBER 6, 2014
REV:

Drawing
E1-01

Sheet 6 of 6