

FOUNDATION/GROUND FLOOR PLAN

0' 1' 5' 10'

SCALE 1/4"=1'-0"

NOTES:

1. ALL CONCRETE REINFORCING STEEL PER PLANS AND SECTIONS.
2. STEP IN TOP OF FOUNDATION WALL IS INDICATED THUS: , AND SHOWS LOWER SIDE OF WALL.
3. SEE S-1.0 FOR STRUCTURAL GENERAL NOTES
4. FOOTING TO BEAR 4'-0" MIN BELOW GRADE.
5. T.O. FOOTINGS ARE INDICATED THUS: (XX'-XX")
6. STEP IN TOP OF FOOTING IS INDICATED THUS: , AND SHOWS LOWER FOOTING.
7. ALL EXPOSED STEEL TO BE HOT DIP GALV. -TYP.

FOOTING SCHEDULE

MARK	SIZE	REINFORCING
TYP	2'-2" W x 10" D x CONT.	#4 @ 32" TRANS, (3) #4 CONT.
F2.5	2'-6" x 2'-6" x 10" D	#4 @ 12" EACH WAY
F3.5	4'-6" x 4'-6" x 10" D	#5 @ 12" EACH WAY
F5	6'-0" x 6'-0" x 1'-0" D	#5 @ 12" EACH WAY

STATE OF MAINE
AARON C. JONES
No. 10968
LICENSED
PROFESSIONAL ENGINEER
April 15th, 2014

kevin browne ARCHITECTURE
7 breezy hill lane
falmouth, me 04105
207.847.3490
kevin@kevinbrowne architecture.com

Reviewed for Code Compliance
Inspection Division
Date: 08/04/14

REVISIONS:

CONSULTANTS:

Structural Integrity
Consulting Engineers
75 Oak Street
Portland, ME 04101
p. 207-774-4654
f. 207-774-4655
www.structuralintegrity.com

BUILD WITH CONFIDENCE!
#3900 Lic. C-Inc. PE

SI # 14-0340

BEAULIEU RESIDENCE

ADDRESS: LOT 46
GREAT DIAMOND ISLAND, ME

CLIENT: RON & LORI BEAULIEU

FOUNDATION PLAN

REV. 1 - 06/18/14
DATE: 04/14/2014
DRAWN: MKL
PROJECT NO.: 2013-14
SCALE: 1/4" = 1'-0"

S1.1