NOTES:
1. PROVIDE SIMPSON JOIST HANGERS AT ALL JOIST ENDS, TYP.
2. WINDOW HEADERS SHALL BE (3)-2x8's w/ ½" PLYWOOD LAMS, U.N.O.
3. PROVIDE (3)-2x6 COLUMNS, U.N.O.
4. SEE TYPICAL FLOOR/ROOF SHEATHING DETAIL THIS SHEET.

NOTES FOR TYPICAL FLOOR/ROOF SHEATHING DETAIL:
1. SEE S0.0 FOR WOOD NOTES FOR SHEATHING REQUIREMENTS.
2. USE APA RATED ⅝-INCH PLYWOOD SHEATHING ON ROOF. USE APA RATED ¾-INCH PLYWOOD SHEATHING ON FLOOR.
3. ATTACH ROOF AND FLOOR DIAPHRAGMS W/10d NAILS SPACED 12" o.c. ALONG INTERMEDIATE FRAMING MEMBERS AND 6" o.c. AT SUPPORTED EDGES.
4. FLOOR AND ROOF DIAPHRAGMS ARE UNBLOCKED, EXCEPT AS NOTED ON ROOF FRAMING PLAN.
5. USE SHEATHING CLIPS BETWEEN SHEETS ON ROOF WHERE BLOCKING IS NOT REQUIRED.

TYPICAL FLOOR/ROOF SHEATHING DETAIL

PLAN LEGEND
- BEARING WALL
- SHEAR WALL
- BEAM
- HSS COLUMN
- COLUMN FROM ABOVE
- COLUMN BELOW
- COLUMN ABOVE AND BELOW
- HOLD-DOWN

ROOF FRAMING PLAN

SCALE: 1/4"=1'-0"

PRINTED: Sep 29, 2015

CASCO BAY ENGINEERING
424 Fore Street
Portland, ME 04101
Phone 207.842.2800
Fax 207.842.2828
www.cascobayengineering.com

CLIENT:
KAPLAN THOMPSON ARCHITECTS
424 FORE STREET
PORTLAND, ME 04101

STATE OF MAINE
ANTHONY DUMAIS
No. 12851
LICENSED
PROFESSIONAL ENGINEER

LAPIERRE ADDITION
56 WEYMOUTH WAY
GREAT DIAMOND ISLAND, MAINE
RESIDENTIAL ADDITION

ISSUED

No.	DESCRIPTION	DR. BY	CKD. BY	DATE
0	ISSUED FOR PERMIT	TD	TD	10-1-15

SHEET TITLE:
ROOF FRAMING PLAN

DESIGNED:	TD
DRAWN:	TD
DATE:	8-11-15
PROJECT NUMBER:	15-132

S1.2