LAP

10/01/2015

1 LONG SECTION

NOT TO SCALE

2 MASTER_STORAGE SECTION

NOT TO SCALE

3 BATHROOM SECTION

NOT TO SCALE

ASSEMBLY NOTES

A PITCHED ROOFS: **~R-50.4**
Standing Seam Metal Roof, On 5/8" Sheathing, On 1x Cross Strapping, On 1x Strapping Run With Slope, On Grace Ice & Water Shield, On 5/8" Plywood Sheathing (Air Barrier, Taped and Sealed), On TJI's w/ Sistered On 2x4 Cedar Rafter Tails w/ D.P. Cellulose Insulation, On Wood Ceiling w/ Exposed False Rafters (species/spacing TBD), Sealed (Stained? TBD)

B PITCHED ROOF (@ EAVES):
Standing Seam Metal Roof, On 5/8" Sheathing, On 1.5" x 2 1/8" Cedar Cross Strapping, On 2x4 Cedar Rafter Tails to Continue 12' Back.

C LOW-SLOPE ROOF: **~R-51**
EPDM Membrane Roof, On Roofing Underlayment, On Grace Ice & Water Shield HT, On Tapered **EPS** Rigid Insulation, On 3 1/2" **EPS** Insulation w/ 2x4 Cedar Rafter Tails Between, On "Zip System Roof Sheathing" w/ Taped Seams (Air Barrier)(See Struct.), On 5.5" Versalam w/ D.P. Cellulose Insulation, On GWB Ceiling.

D EXTERIOR WALL TYPE 1: **~R-32**
Exterior Siding Type 1:Galvanized Corrugated Metal-Vertical Orientation, 7/8" Profile - Match Existing; On 1x3 K.D. Vertical Strapping Rainscreen, On Weather Resistant Barrier (WRB) (incl. Cora-Vent Or Black Vinyl Bug Screen @ Top and Bottom of Wall incl. above win. heads, and below win. sills), On 2.0" R-13 Foil-Faced Poly-Iso Rigid Insulation, On Zip System Wall Sheathing w/ Taped Seams (Air Barrier), On 2x6 Stud Wall (See Struct.) w/ Full-Depth D.P. Cellulose (R-19), on GWB.

E EXTERIOR WALL TYPE 2: **~R-32**
Exterior Siding Type 2: 2'x4' Nominal 3/16" Cor-Ten Panels (Match Existing incl. A325 Type 3 (CorTen) Bolts w/ 7/8" Head and Type 3 Washers) (See Elevations for Extents), On 1x3 K.D. Vertical Strapping Rainscreen (incl. Cora-Vent Or Black Vinyl Bug Screen @ Top and Bottom of Wall incl. above win. heads, and below win. sills), On Weather Resistant Barrier (WRB), On 2.0" R-13 Foil-Faced Poly-Iso Rigid Insulation, On Zip System Wall Sheathing w/ Taped Seams (Air Barrier), On 2x6 Stud Wall (See Struct.) w/ Full-Depth D.P. Cellulose (R-19), on GWB.

F CONC. FOUND. WALL: **~R-8**
Free Draining Backfill, On Galvanized Sheet Metal, On 2" Rigid EPS Insulation, On Fluid-Applied Damp-proofing, On Reinforced Concrete Wall (See Struct.)

G INTERIOR SLAB ON GRADE: **~R-17**
Sealed, Polished, Fiber-Mesh-Reinforced 4" Concrete Slab (See Struct), On 15 Mil. min. Poly Vapor Barrier Taped and Sealed, On 4" Rigid EPS Insulation, On 6" Crushed Gravel Fill (No Fines)

LICENSED ARCHITECT
PHILIPPE J. KAPLAN
No.2567
STATE OF MAINE

KAPLAN THOMPSON
ARCHITECTS
424 FORE ST., PORTLAND, ME 04101
207-842-2888 FAX:842-2828

FOR PERMIT/ CONSTRUCTION

PROJECT: LAPIERRE ADDITION, BRUCE LAPIERRE, GREAT DIAMOND ISLAND, ME	DRAWING:	BUILDING SECTIONS	
	SCALE:	AS NOTED	DRAWN BY: JB
	DATE:	OCTOBER 01, 2015	REVISED:

A-3.1