LAP

10/01/2015

1 ENTRY SECTION

NOT TO SCALE

WINDOW SCHEDULE

ID	Elevation	Width	Height	Quantity	Area	Type	Model #	Manufacturer	Material	Glazing	SHGC	U-Value	Egress	Tempered	Notes
01		3'-3 3/8"	2'-5 1/2"	1	8.24	AWNING		LOEWEN	METAL CLAD FIR	TRIPLE	0.38	0.18			
02		6'-6 3/4"	2'-5 1/2"	1	16.37	AWNING		LOEWEN	METAL CLAD FIR	TRIPLE	0.38	0.18			
03A		6'-6 3/4"	2'-5 1/2"	1	16.37	AWNING		LOEWEN	METAL CLAD FIR	TRIPLE	0.38	0.18			
03B		6'-6 3/4"	5'-3"	1	34.81	FIXED		LOEWEN	METAL CLAD FIR	TRIPLE	0.48	0.16			
04		6'-6 3/4"	2'-5 1/2"	1	16.37	AWNING		LOEWEN	METAL CLAD FIR	TRIPLE	0.38	0.18			
05		6'-6 3/4"	7'-1 5/8"	1	47.26	CASEMENT, FIXED HIGH		LOEWEN	METAL CLAD FIR	TRIPLE	0.48	0.18	YES	CASEMENTS ONLY	
06		6'-6 3/4"	7'-1 5/8"	1	47.26	CASEMENT, FIXED HIGH		LOEWEN	METAL CLAD FIR	TRIPLE	0.48	0.18	YES	CASEMENTS ONLY	
07		6'-6 3/4"	2'-5 1/2"	1	16.37	AWNING		LOEWEN	METAL CLAD FIR	TRIPLE	0.38	0.18			
08		6'-6 3/4"	2'-5 1/2"	1	16.37	AWNING		LOEWEN	METAL CLAD FIR	TRIPLE	0.38	0.18			
09		6'-6 3/4"	2'-5 1/2"	1	16.37	AWNING		LOEWEN	METAL CLAD FIR	TRIPLE	0.38	0.18			
10		6'-6 3/4"	2'-5 1/2"	1	16.37	FIXED		LOEWEN	METAL CLAD FIR	TRIPLE	0.48	0.16			
				11	**252.16 sq ft**										

DOOR SCHEDULE

ID	Elevation	Width	Height	Thickness	Quantity	Model #	Manufacturer	Type	Finish	Glazing	Notes
01		3'-0"	6'-8"	0'-1 1/4"	2			POCKET			
02		4'-0 1/2"	7'-0"	0'-1 1/4"	1			POCKET			
03		3'-0"	6'-8"	0'-1 3/8"	1			SWING			
04		2'-0"	6'-8"	0'-1 3/8"	1			SWING			
05		3'-0"	7'-0"	0'-1 1/4"	1			POCKET			
E1		3'-6"	7'-2"	0'-1 3/4"	1		LOEWEN	ENTRY SWING		YES	TEMPERED
E2		5'-10 7/8"	7'-2"	0'-1 3/4"	1		LOEWEN	ENTRY SLIDER		YES	TEMPERED
E3		6'-0"	6'-0"	0'-1 1/4"	1						SHED DOORS - UNINSULATED
					9						

LICENSED ARCHITECT
PHILIPPE J. KAPLAN
No.2567
STATE OF MAINE

KAPLAN THOMPSON
ARCHITECTS
424 FORE ST., PORTLAND, ME 04101
207-842-2888 FAX:842-2828

FOR PERMIT/ CONSTRUCTION

PROJECT:
LaPierre Addition
Bruce LaPierre
Great Diamond Island, ME

DRAWING: BUILDING SECTIONS / SCHEDULES
SCALE: AS NOTED
DRAWN BY: JB
DATE: OCTOBER 01, 2015
REVISED:

A-3.2