FIRST FLOOR LEVEL - APPROXIMATELY 6' ABOVE BASEMENT FLOOR. BASEMENT FLOOR SLAB APPROXIMATELY 4' BELOW GRADE

POST #1 - 3 1/2" X 5 1/4" LVL W/SIMPSON EPC 67 POST CAP AND SIMPSON PC47 POST BASE

POST #2 - (4) 2X4

POST #3 - (2) 2X4 WITH 1/2" PLYWOOD

POST #4 - 6X6 WITH SIMPSON ABW447 POST BASE

POST SCHEDULE

1 First Floor Framing Plan
1/4" = 1'-0"

Inspections Division
Date: 10/30/17

S

DATE: 10-16-2017

First Floor Framing - Foundation Footings

79 Island Ave
Peaks Island, Maine 04108