



Permitting and Inspections Department
Michael A. Russell, MS, Director

May 20, 2017

SUTTON KERRY & LARRY STOLTZ &
906 CONSTITUTION AVE NE
WASHINGTON, DC 20002

CBL: 084 N029001
Located at: 41 NEW ISLAND AVE

Certified Mail

Dear SUTTON KERRY & LARRY STOLTZ & ,

An evaluation of the above-referenced property on **06/21/2016** shows that the structure fails to comply with Chapter 6.Article V. of the Code of Ordinances of the City of Portland, The Housing Code. Attached is a list of the violations.

This is a notice of violation pursuant to Section 6-118 of the Code. All referenced violations shall be corrected within **30** days of the date of this notice. A re-inspection of the premises will occur on **06/24/2017** at which time compliance will be required. Failure to comply will result in this office referring the matter to the City of Portland Corporation Counsel for legal action and possible civil penalties, as provided for in Section 1-15 of the Code.

This constitutes an appealable decision pursuant to Section 6-127 of the Code.

Please feel free to contact me if you wish to discuss the matter or have any questions.

Please be advised that the Portland City Council has amended the Building regulations to include a \$150.00 re-inspection fee. This violation will automatically cause a re-inspection at no charge. If there are any subsequent inspections, however, the \$150.00 fee will be assessed for each inspection.

Sincerely,

/s/

A handwritten signature in black ink, appearing to read "Kevin Hanscombe", written over a horizontal line.

Kevin Hanscombe
Code Enforcement Officer

**CITY OF PORTLAND
HOUSING SAFETY OFFICE**

389 Congress Street
Portland, Maine 04101

Inspection Violations

Owner/Manager SUTTON KERRY & LARRY STOLTZ &		Inspector Matthew Sarapas	Inspection Date 6/21/2016
Location 41 NEW ISLAND AVE	CBL 084 N029001	Status Reinspect	Inspection Type Housing Safety Inspection

Code	Int/Ext	Floor	Unit No.	Area	Compliance Date
-------------	----------------	--------------	-----------------	-------------	------------------------

1) 205

Violation: SMOKE ALARMS / LEVEL; Smoke Alarms - One and Two-Family Dwellings: Single-station or multiple-station (interconnected) photoelectric smoke alarms must be powered by the building electrical system or powered by a 10-year non-replaceable battery and shall be positioned correctly on walls or ceilings: (1) within 21 feet of any door to a sleeping room and (2) in living areas separated by doors on each level of the dwelling unit and (3) including the basement.

NFPA 101 (2009) 24.3.4.1(2)(3), 9.6.2.10, amended by City Code of Ordinances Section 10-3(i)

Notes: First and second floor need smoke detectors

2) 206

Violation: SMOKE ALARMS / BEDROOMS; Smoke Alarms - One and Two-Family Dwellings: Single-station or multiple-station (interconnected) photoelectric smoke alarms must be powered by the building electrical system or powered by a 10-year non-replaceable battery and shall be positioned correctly on walls or ceilings: in all sleeping rooms.

NFPA 101 (2009) 24.3.4.1(1), 9.6.2.10, amended by City Code of Ordinances Section 10-3(i)

Notes: Bedrooms x2 need smoke detectors

3) 207

Violation: CARBON MONOXIDE ALARMS / LEVEL; Carbon Monoxide Alarms - One and Two-Family Dwellings: Single-station or multiple-station (interconnected) Carbon Monoxide alarms must be powered by the (A) building electrical system, or (B) 10-year non-replaceable battery and shall be positioned correctly on walls or ceilings: (1) on each level of the dwelling unit, and (2) including the basement.

NFPA 720 (2009) 9.5.1, 9.5.3, amended by State Law Title 25, Chapter 317 § 2468

Notes: First and second floor need co detectors

4) 210

Violation: ESCAPE WINDOWS; Escape Windows - One and Two-Family Dwellings: Escape windows shall be a free and clear outside window or door operable from the inside without the use of tools, keys, or special effort. Windows shall be within 20 feet of the finished ground level or accessible by rescue apparatus (if approved), or opening onto an exterior balcony and when below ground level shall be provided with an accessible, free and clear, window well.

NFPA 101 (2009) 24.2.2.3.3

Notes: One bedroom egress window undersized

Comments: