



Walk-In Cooler to made of :

4" foam board Insulation floor, walls, ceiling.
 1/2" plywood walls, ceiling 3/4" floor.
 Floor, walls, ceiling to be coated with UCoat-AM epoxy.
 Ucoat-AM is an antimicrobial product that is USDA and FDA approved.

Cove molding on the floor to wall transitions

NO floor drain

Use existing door, with inside release

Lights to be vapor proof with cage cover

New exterior wall:
 2x4 wall framing with
 3/8" plywood sheathing
 cedar shingles

New floor to be same as level as rest
 of building. Built over existing floor.

Revised pages 8 & 10 as per inspector review original 2x6 floor joists now 2x8 joists

Not to Scale

Parcel ID 084 Q003001 Location 6 Welch Street Peaks Island, ME Land Use Retail & Personal Service Zoning IB Legal 84-Q-3-5 to 8, 6 Welch St, Peaks Island Lot Area 25,220 SF	Proposed Cross Section 3	
	Walk-in Cooler Re-build Enclosure	
	revised 15 mar 13	pg 8