

DOOR / WINDOW SCHEDULE

Door Schedule

Qty	Floor	Size	Width	Manufacturer	Height	R/O	Description	Header	Thickness
1	1	2668 L IN	30 "		80 "	32"x82 1/2"	Hinged-Door P04	2x6x35" (2)	1 3/8"
1	1	3068 L EX	36 "		80 "	38"x83"	ext. Hinged-Door E02	2x6x41" (2)	1 3/4"
1	1	6068 R EX	72 "		80 "	74"x83"	ext. Slider-Glass	2x10x77" (2)	1 3/4"

Window Schedule

	Qty	Floor	Size	Width	Height	R/O	Egress	Description	Header	Code	Manufa
DH	1	1	2340DH	27 "	48 "	28"x49"		Double Hung	2x6x31" (2)		
AW	3	1	2621AW	30 "	25 "	31"x26"		Awning	2x6x34" (2)		
DH	1	1	2640DH	30 "	48 "	31"x49"		Double Hung	2x6x34" (2)		
DC	1	1	5640DC	66 "	48 "	67"x49"		Dbl Casement-lhl/rhr	2x8x70" (2)		

REVISION TABLE	NUMBER	DATE	REVISION	BY	DESCRIPTION

REBUILD BUNK HOUSE

CLIENT: KEVIN CARTER
24 OAK STREET PEAKS ISLAND ME

DRAWINGS PROVIDED BY:
MCTIGUE CONSTRUCTION

DATE:

2/22/2017

SCALE:

SHEET:

P-10