CROSS SECTION

8/12 ROOF PITCH
ASPHALT ROOF SHINGLES
ICE + WATER SHEILD
8" ALU. DRIP EDGE
5/8" ADVANTECH ROOF SHEATHING
2X10 RAFTERS 16" OC, SIMPSON HURRICAN
CLIPS ON EACH

2X6 WALL STUDS 16" OC
1/2" ADVANTECH WALL SHEATHING
R 21 WALL INSULATION
TYPAR HOUSE WRAP
VINYL SIDING

RAILING HEIGHT 36"

TREAD 11"

RISE
7 1/4"

GRADE

LEDGE

R 49 CEILING INSULATION
2X6 CEILING JOIST 16" OC
FASTENED WITH
SIMPSON +H2 NAILING
FASTNERS

2X12 FLOOR JOIST 16" OC
DOUBLE 2X12 BOX SILL

6X6 PT POST
6X6 SIMPSON POST BASE

12" DIAMETER CONCRETE SONO TUBE
ON LEDGE PINNED WITH 3-#4 X 24"
REBAR 10" INTO LEDGE, 14" INTO
CONCRETE TUBE

Reviewed for Code Compliance
Inspections Division
Approved with Conditions
Date: 05/16/17

REVISION TABLE			
NUMBER	DATE	REVISED BY	DESCRIP

REBUILD BUNK HOUSE

CLIENT: KEVIN CARTER
2-4 OAK STREET PEAKS ISLAND ME

DRAWINGS PROVIDED BY:
MCTIGUE CONSTRUCTION

DATE:
5/7/2017

SCALE:

SHEET:
P-7