3 TRUSS HEEL REINFORCEMENT DETAIL
1 1/2"=1'-0"

2 TRUSS SPLICE REINFORCEMENT DETAIL
1 1/2"=1'-0"

1 FIRST FLOOR WALL FRAMING PLAN
1/8"=1'-0"

STRUCTURAL NOTES

- FOUNDATION, FLOOR, & ROOF FRAMING PLANS & DETAILS PER APPROVED STRUCTURAL DRAWINGS OF 03.20.2017.
- TYP @ EXTERIOR WALLS, NEW 2x4 WALL BUILT TO INTERIOR OF EXISTING TO PROVIDE DEPTH FOR INSULATION. SEE 2/A4.1.
- TWO JACKS STUDS AT ALL EXTERIOR HEADER OPENINGS GREATER THAN 3'-0".
- INTERIOR HEADERS (2) 2x4, TYP.

CITY OF PORTLAND, MAINE — RESURGAM

Reviewed for Code Compliance
Inspections Division
Approved with Conditions

Date: 04/24/18

Rachel Conly
26 Sterling S
Peaks Island,
207.766.562
www.rachelco

DATE	NOTES
2017.12.29	ISSUED FOR PERMIT
REVISED	

PROJECT NORTH

PROJECT
2 Island Ave.
Peaks Island, ME

FIRST FLOOR WALL FRAMING PLAN

S1.1