Reviewed for Code Compliance
Inspections Division
Approved with Conditions
Date: 04/20/16

Scope of plumbing to be done

1. Master bath
   a. Extend existing drain for shower to accommodate new shower.
   b. Remove existing plumbing for toilet and plumb for new location
   c. Extend existing plumbing for vanity to include another sink and soaking tub including drain line for tub.
   d. Remove existing lines for the radiant heaters and run new lines on both exterior walls of proposed master bath.
   e. Insulate all supply lines with foam coverings (even inside walls or joists)
2. Extension of master bath into porch area.
   a. Connect onto supply of radiant heat line on the existing wall going into house.
   b. Run new line into proposed extension and put a 12ft section of baseboard heat along the existing wall.