Reviewed for Code Compliance
Inspections Division
Approved with Conditions
Date: 04/20/16

Scope of West Bedroom Remodel

1. Remove existing wall between the two bedrooms.
2. Remove the two closets just outside bedrooms.
3. Remove the existing two windows.
4. Frame in for new windows.
5. Remove one door going into bedroom.
6. Frame in to seal that door.
7. Frame in wherever necessary to piece sheetrock back in
8. Piece tongue and groove flooring back in where wall came out (if necessary)
9. Install new window
10. Build new built in cabinets on each side of bedroom
11. Sheetrock and Tape where necessary
12. Install new trim moldings around windows
13. Paint