



Outdoor Unit – Master Bedroom
 Located on blocking on the second floor deck just outside the master bedroom.

Weight of unit is 88 lbs. Shall be mounted to decking material

Indoor Unit – Finished Basement
 Located in the southeast corner high on the wall.

Weight of unit is 22 lbs. Unit to be mounted to wall framing with 2.5" fasteners sufficient to support the unit.

Indoor Unit – 1st Fl.
 Located in living room high up on the exterior wall

Weight of unit is 22 lbs. Unit to be mounted to wall framing with 2.5" fasteners sufficient to support the unit.

Outdoor Unit – 1st Fl.
 Located at ground level and will be mounted to a self supporting stand on concrete blocks.

Weight of unit is 88 lbs.

Notes:
 Home is built of traditional wood framing and is sufficient to support the additional load of the equipment being installed.

ReVision Energy 142 Presumpscot Street Portland, Maine, 04097 207-221-6342		HVAC Equipment Layout			
		Paul Castle 308 Seashore Avenue, Peaks Island, ME			
DATE 6/17/2014	DRAWN BY Geoff Sparrow	PAGE 1 of 1	DWG# 1	Rev. 0	