



A
TEMPERED
FROSTED (DESIGN T.B.D.)

Rachel Conly Design LLC
26 Sterling Street
Peaks Island, Maine 04108
207.766.5625

DATE	REVISION	NOTES
2016.11.07		

1/2" = 1'

PROJECT
Scott Residence
Peaks Island, ME
04108

A Proposed Doors and Windows: LOGIC Brand, CPVC (and site-built skirting access doors)

Notes:

- Contractor to verify all existing rough openings and proposed door and window sizes, before placing order.
- Contractor to verify R.O.s of doors and windows with vendor/manufacturer before framing or modifying any door and window openings.
- Finished door and window headers are to align per floor.
- Door sizes may need to be adjusted to allow for header alignment, depending upon actual existing header heights.
- Factory applied exterior extension jambs and interior drywall return pockets are assumed. See detail 17e.
- Skirting access doors E and F, are to be clad in place, along with adjacent skirting, so that boards and gaps align. Kerf skirting boards around doors after cladding.

SK1
Proposed
Doors
& Windows