



The Iron Shop 5-ft Houston Black Baked Enamel Interior Spiral Staircase Kit

Item #: 381913 | Model #: HB5013

5-ft Houston Black Baked Enamel Interior Spiral Staircase Kit

- Made in the USA
- Interior application with simple installation instructions, step-by-step DVD and all hardware included
- This model is designed to meet the International Residential Building Code - contact your local building department for your local code requirements (code-compliant models includes safety-return handrail ends and riser bars)
- Stairs can go through a well opening (minimum finished well opening 52" square) or off the side of a balcony or loft
- Standard model will work from 7' 4" to 10' 3" (height can be increased to 12' 8" with additional risers sold separately HB50AR)
- Kit includes: smooth-plate steel 30° treads and 31" square landing, 3/4" square spindles-heavy wall tubing with less than 4" opening between spindles, center pole, landing rail (rail connected to center pole), and hardware
- Additional rails sold separately: balcony rail (second rail on landing-HB50BR) and level rail (30 panel with 2 posts HB30PP)

Center Pole Diameter (Inches)	3.5
Color	Black baked enamel
Design Name	Houston
Handrail Dimensions	1.25" outside diameter
Handrail Material	Aluminum coil
Height Range	7-ft 4-in to 10-ft 3-1/2-in
Interior/Exterior	Interior
Rise Between Treads (Inches)	9.5
Size - Measurement (Feet)	5.0

Attachment Method	Concrete
Stair Case Diameters	5-ft
Standard	Yes
Tread Length (Inches)	26.375
Tread Material	12-gauge smooth plate steel
Tread Thickness (Inches)	0.105
Turn of Spiral	Clockwise or counterclockwise
Warranty	5-year from date of purchase on manufacturer defects
Weight Capacity (lbs.)	700.0