



FOOTING:

TYPICAL: DECK PIER
 6" ϕ CONCRETE, TO
 LEDGE W/ #4 REBAR PINED (TO LEDGE)
 W/ (1) #4 REBAR VERTICAL
 W/ SIMPSON POST BASE TO (ZMAX)
 ANCHOR (2) 2x8 PT FLASH
 FRAMED STRUCTURE

FRAMING:

2x8 P.T. @ 16" OC
 (FLASH FRAME)
 (SIMPSON LVS2X6
 ZMAX
 JOIST HANGERS)
 TYP.

DECKING:

1x4 MERANTI
 W/ S.S. TRIM HEAD SCREWS
 W/ 1x4 MERANTI SKIRT,
 BOTH SIDES

HEIGHT: (NO CHANGE)

FINISH GRADE IS 28" OR LESS
 BELOW THE WALKWAY.
 NO GUARD RAIL IS REQUIRED
 NO STEPS (FLASH)



RE: BRENNA HEAPS + TODD HEASLEY / DOUG WILBUR BUILDER : 20 PARK AVE, PEAKS ISLAND

SCOPE: **AMENDED ENTRY WALKWAY:**

PERMIT: PERMIT ID: 2013-02567

CHANGE DESCRIPTION: CHANGED ENTRY WALKWAY IS SHORTER THAN
 THE ORIGINAL PERMITTED VERSION, AND IS AT AN ANGLE TO THE BUILDING.
 NO OTHER CHANGE

CONTACT: WINKELMAN ARCHITECTURE, WILL WINKELMAN CELL: 207.232.6831 WILL@WINKARCH.COM