Inspections Division
Date: 09/10/15

TUB PLATFORM FRAMING BELOW

0' 1' 2' 4' 6'

3/8" SCALE

DECK FRAMING PLAN

FRAMING:

- ALL FRAMING IS TO BE P.T. SYP #2 OR BTR, TYP.
- LVL IS P.T.
- HOT DIP GALV FASTENERS
- SIMPSON CORROSION RESISTANT HANGERS AS NOTED (VERIFY)

CONCRETE:

10" ϕ CONC. PIERS WITH (1) #4 BAR. WIDEN AT BEARING (LEDGE) WITH 'BIG FOOT FORM, OR SIMILAR) LEDGE IS ANTICIPATED (OR SET BELOW 48" W, W/ 8"W x 18"x18" FTG.). DRILL + PIN TO LEDGE W/ (1) #4 BAR

REGISTERED ARCHITECT
WILLIAM R. WINKELMAN
#1543
STATE OF MAINE

FRAMING PLAN | **A1.002**

HEAPS - HEASLEY HOUSE | Deck & Hot Tub Addition - 20 Park Ave, Peaks Island, ME - 31 July 2015 | WINKELMAN ARCHITECT